

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02084-00-00⁰¹
Spot: NWNESW Sec/Twnshp/Rge: 12-10S-20W
2310 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: SUTOR B Well Number: 4
County: ROOKS Total Vertical Depth: 3742 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet: 121.62
Surface Casing: Size 8.625 feet: 1630 800 SX CMT
Production: Size 5.5 feet: 3738 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/13/2001 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel -500# hulls.
Sand bottom to 3550' plus 5 sxs cement.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/13/2001 2:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Shot casing at 2500' - pulled casing to 2150' - spotted 150 sxs cement with 300# hulls mixed in cement.
Pulled casing to 1650' - spotted 40 sxs plus 100# hulls.
Pulled casing to 950' - spotted 40 sxs cement plus 100# hulls.
Pulled casing to 200' - spotted 45 sxs cement to circulate at surface.
Pulled casing with cement in cellar.
Job complete.

INVOICED
DATE 03-08-2001
INV. NO. 2001061471

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: ALLIED CEMENTING COMPANY.

2-28-01
FEB 28 2001

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel
(TECHNICIAN)

CONSERVATION DIVISION

"B"


SOHIO PETROLEUM ET AL #4 SUTOR B 12-10-20W 22
NW NE SW

Contr. RESERVE DRILLING COMPANY ROOKS County

E 2192 Comm. 7-20-50 Comp. 9-22 50 IP 227 BOPD

Tops	Depth	Datum	Casing		PHY POT
ANH	1620	+ 572	8" 1629	DP 3742	
HEEB	3108	- 1216	5" 3738	SWB 14 BOPH/5 HRS	
LANS	3443	- 1251			
CONG	3681	- 1489			
SIMP	3719	- 1527			
ARB	3737	- 1545			
T.D.	3742	- 1550			

BERLAND POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS