

STATE OF KANSAS
STATE CORPORATION COMMISSION
10 S. Market, Room 2078
Topeka, KS 66602

WELL PLUGGING RECORD
K.A.R.-02-3-117

15-051-01485-00-01

API NUMBER Spud Date 8-23-64

LEASE NAME Schwab

WELL NUMBER #1

1650 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 8 TWP. 12S RGE. 20W (E) or (W)

COUNTY Ellis

Date Well Completed

Plugging Commenced 2-19-99

Plugging Completed 2-24-99

LEASE OPERATOR Carl Boxberger Oil, Inc.

ADDRESS P.O. BOX 1604 Great Bend, Kansas 67530

PHONE (316) 793-6032 OPERATORS LICENSE NO. 4707

Character of Well

Oil, Gas, D&A, SWD, Input, Water Supply Well

The plugging proposal was approved on (date)

Roger Moses (KCC District Agent's Name)

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4029'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	218'	None
				5-1/2"	4029'	600'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each. Plugged off bottom with sand to 3500' and 5 sks. cement. Shot well @2000', pumped 100 sks. cement & 300# hulls, displaced to 650'. Shot @600', mixed 50 sks. cement and 100# hulls, pulled to 200' and circulated 75 sks. cement to surface. 60/40 pos. 10% gel. Plugging Complete

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Carl Boxberger Oil, Inc.

State of Kansas County of Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

Above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 26th day of February, 1999

Irene Herzberg
Notary Public

My Commission Expires:



Form 37
Revised 05-