


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Ellis County. Sec. 8 Twp. 12 Rge. 20 /E) W (W)  
Location as "NE/CNW/SW" or footage from lines NW/4 NW/4 NE/4  
Lease Owner Transit Corporation  
Lease Name Schoenthaler "E" Well No. #1  
Office Address 1516 Liberty Bank Bldg., Okla. City, Okla.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 2-19 1956  
Application for plugging filed 2-19 1956  
Application for plugging approved 2-19 1956  
Plugging commenced 2-19 1956  
Plugging completed 2-19 1956  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3994 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 184'   | None       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole to 180 ft. with heavy drilling mud, set plug and cemented with 15 sacks cement. Filled hole to 40 ft. with heavy drilling mud, set plug and cemented to bottom of cellar with 10 sacks cement.

03-01-1956  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Transit Corporation  
Address 1516 Liberty Bank Bldg., Okla. City, Okla.

STATE OF Okla., COUNTY OF Oklahoma, ss.  
C. W. Dodson (employee of owner) ~~OKLAHOMA~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Dodson  
Okla. City, Oklahoma.  
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of February, 1956

My commission expires Jan. 28, 1959 Irene A. Grady Notary Public.

**PLUGGING**  
FILE SEC 8 T 12 R 20  
BOOK PAGE 41 LINE 23

15-051-01041-00-00

DRILLER'S LOG

SCHOENTHALER NO. E #1.

NW NW NE Sec. 8-12S-20W.,  
Ellis Co., Kansas

Elevation: 2269 DF  
Commenced: 2-7-56  
Completed: 2-19-56

| <u>FORMATION</u>    | <u>FROM</u> | <u>TO</u>  |
|---------------------|-------------|------------|
| Surface Clay & Sand | 0           | 120        |
| Shale & Shells      | 120         | 184        |
| Shale & Shells      | 184         | 1204       |
| Sand                | 1204        | 1430       |
| Shale & Shells      | 1430        | 1680       |
| Anhydrite           | 1680        | 1720       |
| Shale & Shells      | 1720        | 1850       |
| Shale & Red Bed     | 1850        | 2050       |
| Shale               | 2050        | 2355       |
| Lime & Shale        | 2330        | 2544       |
| Lime                | 3560        | 3600       |
| Lime & Shale        | 3600        | 3638       |
| Lime                | 3638        | 3775       |
| Lime & Shale        | 3775        | 3910       |
| Lime                | 3910        | 3943       |
| Conglomerate        | 3943        | 3966       |
| Lime, Arbuckle      | 3966        | 3994 T. D. |

Ran 9 Jts. 8-5/8" surface casing,  
cemented w/ 125 sx. cement

**Formation Tops:**

Arbuckle 39660

FILED  
03-01-1956

I hereby certify the foregoing to be a true and accurate Driller's Log of the formations encountered in the above well.

TRANSIT CORPORATION

BY C. W. Dodson

Subscribed and sworn to before me this 28th day of February 1956.

Jrene A. Brady  
Notary Public,  
State of Oklahoma

**PLUGGING**  
FILE SEC 8 T 12 R 20W  
BOOK PAGE 41 LINE 23