

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-21,682-00-00

LEASE NAME Reitmayer

WELL NUMBER 1

SPOT LOCATION SE SE SW

SEC. 17 TWP. 12 RGE. 20 (W) or (W)

COUNTY Ellis

Date Well Completed 5-12-79

Plugging Commenced 5-3-84

Plugging Completed 5-3-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR N-B Company, Inc.

ADDRESS Box 506, Russell, KS 67665

PHONE # (913) 483-5345 OPERATORS LICENSE NO. 6111

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? 6

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation Marmaton Depth to top bottom T.D. 3980

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	218'	-0-
Marmaton				4-1/2"	3928'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

150 sks 50/50 pos. 10% gel, 3% c.c. pumped down casing

150 sks 50/50 pos. 10% gel, 3% c.c. pumped down back side of casing

Maximum pressure reached - 500#

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Emphasis Oil Operations License No. 750
Address Box 506, Russell, KS 67665

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Joe K. Branum

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Joe K. Branum
(Address) Box 506, Russell, KS 67665



SUBSCRIBED AND SWORN TO before me this 7th day of May, 1984

My Commission expires: February 6, 1988

Notary Public

RECEIVED
STATE CORPORATION COMMISSION
MAY 09 1984
CONSERVATION DIVISION
Wichita, Kansas

15-051-21682-00-00

EMPHASIS OIL OPERATIONS

P. O. Box 506
Russell, Kansas 67665

DRILLERS LOG

OPERATOR: N - B Company, Inc.
P. O. Box 506
Russell, KS 67665

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, KS 67665

LEASE: Reitmeier

WELL: #1

LOCATION: SE SE SW
Section 17-12S-20W
Ellis County, Kansas

Total Depth: 3980'

Elevation: 2279' K.B.

Commenced: 4-24-79

Completed: 5-3-79

Casing: 8-5/8" @ 218'
4-1/2" @ 3928'

Status: Oil Well

DEPTHS & FORMATIONS

(All measurements from K.B.)

Soil & Clay	60	Shale	3278
Shale	223	Lime & Shale	3597
Shale & Sand	1640	Lime	3681
Anhydrite	1693	Shale & Lime	3753
Sand & Shale	2063	Lime & Shale	3900
Shale & Shells	2430	Lime (R.T.D.)	3980
Shale & Lime	3080		

STATE OF KANSAS)
COUNTY OF RUSSELL) ss

I, Joe K. Branum, of Emphasis Oil Operations state that the above and foregoing is a true and correct log of the above captioned well.



Joe K. Branum

Subscribed and sworn to before me this 7th day of May, 1979.

My Commission Expires: October 2, 1979.

RECEIVED
STATE CORPORATION COMMISSION
05-09-1984
MAY 09 1984

CONSERVATION DIVISION
Wichita, Kansas


Notary Public