



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 25 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Coldwater of Alpine Drlg. has this

date requested permission to plug the following described well:

Mr. Coldwater guarantees payment of the plugging fee.

Operator's full Name: Alpine Drilling Company

Complete Address: 800 Bitting Bldg., Wichita, Ks.

Lease Name: Schmeidler Well No. 1

Location: SW SE SE Sec. 16 Twp. 12 Rge. (E)(W) 17

County: Ellis Total Depth 3746' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Coldwater was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace

70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sk cmthru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey
Conservation Division Agent