

3 023263

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 100101

Operator: STATE OF KANSAS

Name & FEE FUND PLUGGING

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC.

Lic. # 30670

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00 A.M. Day: 12 Month: 20 2007

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF A 2" LINER CEMENTED INSIDE 4 1/2" CASING

CEMENTED IN 12" SURFACE CASING. THE PLUGGING PROPOSAL WAS TO PERFORATE

THE 4 1/2" CASING AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL

OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____ TECHNICIAN
None ☒

Operations Completed: Hour: 3:00 P.M. Day: 12 Month: 20 2007

Actual Plugging Report: THE WELL WAS PERFORATED AT 200' AND AT 700'.

1" PIPE WAS RAN INTO THE 2" PIPE TO 800'. CEMENT WAS PUMPED INTO THE 1"

PIPE UNTIL CEMENT CIRCULATED FROM THE WELL AT SURFACE. THE 1" PIPE

WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 85 SACKS OF

CEMENT WERE PUMPED INTO THIS WELL.

Remarks: GPS SESSION POINT NO. WEI 17. (THIS WAS WELL NO. DD-30 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION

Signed:

Clayton P. Titel
TECHNICIAN

FEB 04 2008

CONSERVATION DIVISION
WICHITA, KS

2

33749

PPH