

3 023253

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 100 101

Operator: STATE OF KANSAS

Name & FEE FUND PLUGGING

Address _____

AB oil well _____ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC.

Lic. # 30870

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00 A.M. Day: _____ 4 Month: 12 2007

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT HAD

BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE

AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

TECHNICIAN

None X

Plugging attended by Agent: All _____ Part _____

Operations Completed: Hour: 12:00 P.M Day: _____ 4 Month: 12 2007

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 850' CEMENT WAS

PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE.

THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 10" ANNULUS TO 500'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 10"

SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED

FROM SURFACE. 143 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: GPS SESSION POINT NO. WEI 28. (THIS WAS WELL NO. EE-27 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 04 2008

CONSERVATION DIVISION
WICHITA, KS

Clayton P. Titel
TECHNICIAN

Well Master Data

Search T-1's / Letters

Get Cnty
From Local

General

Loc

API Well #

15 001 91771 00 00

Create Next API

Well Doc

Well

Status

AI

DATES FOR THIS API #

District Dkt #

for This Well

Images

History

Stat Source

LGCY

Status Dt

11/21/1941

Lee Nm

WEINER

Well No

EE 27

Type

EOR

Intent Dt

Intent Exp

Oper/Status

1

End

Harris

Work Oper

1

End

C-1 Well Type

Type Cmpl

Dkt / Permit

ED0391 ES

District

03

Lgcy Oper

C-1 Oper

Driller/Status

1

End

Lgcy Driller

KDOR Lease Code:

Oil

Gas

Const

TVD

Kickoff

Plug Back

Hole

Loggers

Master Well File Comments

Date/By Well Comment

Record: 1 of 1

WI Loc 23-26S-18E, 35 FSL 51D FEL

TA Stat

Last Edited: 12/22/05

State Add

Prod-Geo

Strings

Perfs

Stim

Logs

Pluggings

UIC

TA

By:

RBDMSadm

Form View

FLTR

NUM