

3 023273

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 100101

Operator: STATE OF KANSAS

Name & FEE FUND PLUGGING

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC.

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 1:00 P.M. Day: _____ 9 Month: 1 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT HAD

BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE

AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____

TECHNICIAN

None ☒ X

Operations Completed: Hour: 5:00 P.M. Day: _____ 9 Month: 1 2008

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 822' CEMENT WAS

PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE.

THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 475'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 8"

SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED

FROM SURFACE. 151 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: GPS SESSION POINT NO. WEI 35. (THIS WAS WELL NO. GG-23 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 04 2008

CONSERVATION DIVISION
WICHITA, KS

Clayton P. Titel
TECHNICIAN

15-001-02447-00-00

API NUMBER

20080002-035

NE, NE, NE 1/4

Sec/Twp/Rge S.23-T.26S-18E.

4269 feet from south section line

382 feet from east section line

Lease/Well# WEINER NO.GG-23

County ALLEN

Well Total Depth 850' feet

Production Pipe: 2" Size Feet 850'

Surface Casing: 8" Size Feet 20'

E-591 D & A

Lic. #

30670

33749

Well Master Data

Search T-1's / Letters

Get Only
From Local

General Loc

API Well # 15 001 91766 00 00 Create Next API
District Dkt # for This Well Well Doc
Images History

Status AI

Stat Source LGCY

Type EOR

C-1 Well Type

Type Cmpl

Dkt / Permit E0039186

District 03

KDOR Lease Code:

Oil Gas

DATES FOR THIS API #

Status Dt 11/21/1941

Intent Dt

Intent Exp

AC0-1 Spud

Dist Spud

Lag String

TD Rchd

Cmpltd Dt

1st Prod

1st Inj

PB TD Dt

P/A Dt

Const TVD

Kickoff

Plug Back

Hole

Loggers

Lee Nm WEINER Well No GG 23

Oper/Status 1 End Harris

Work Oper: End

Source: Effect Dt Request T-1

Lgcy Oper

C-1 Oper

Driller/Status End

Lgcy Driller

Master Well File Comments

Date/By Well Comment

Record: 1 of 1

WI Loc 23-265-18E, 42 FSL 360 FEL

TA Stat

State Add Prod-Geo Strings Perfs Stim Logs Pluggings UIC TA

Last Edited: 12/22/05

By: RBDMSadm

Form View

FLTR

NUM