

3 023276

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 100100Operator: STATE OF KANSASName & FEE FUND PLUGGING

Address _____

AB oil well _____ Gas Well _____ SWD Well/ Input Well

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC.Address: 19245 FORD RD., CHANUTE, KS. 66720Company to plug at: Hour: 8:00 A.M. Day: _____ 8 Month: 1 2008Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT HADBEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATEAS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____

TECHNICIAN

None XOperations Completed: Hour: 12:00 P.M. Day: _____ 8 Month: 1 2008Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 760' CEMENT WASPUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE.THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 300'.CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 8"SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLEDFROM SURFACE. 65 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.Remarks: GPS SESSION POINT NO. WEI 47. (THIS WAS WELL NO. EE-21 ON THE LEASE MAP.)(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION

Signed:

Clayton P. Titel
TECHNICIAN

FEB 04 2008

CONSERVATION DIVISION
WICHITA, KS

33749

Search T-1's Letters

Get Cnty From Legal



API Well #	15	001	91769	00	00	Create Next API for This Well	Well Doc Images	Well History
District/Dist #								
Lee Nm	WEINER					Well No.	EE 21	
Oper/Status	1	▼	End	Harris				
Work Oper:		▼	End					
Source:			▼	Effect Dt:			Request T-1	
Lgcy Oper								
C-1 Oper								
Driller/Status		▼	End					
Lgcy Drllr								

Status	AI
Stat Source	LCGY
Type	EOR
C-1 Well Type	
Type Compl	
Dkt / Permit	E00521 21
District	03
KDOR Lease Code:	
Oil	Gas

Status Dt	11/21/1941
Intent Dt	
Intent Exp	
ACG-1 Spud	
Dist Spud	
Lang String	
TD Rchd	
Completed Dt	
1st Prod	
1st Inj	
FB TD Dt	
P/A Dt	

Date/By	Well Comment

Record: 1 of 1

TA Stat

State Add.	Prod-Geo	Strings	Perfs	Stim	Logs	Pluggings	UIC	TA
------------	----------	---------	-------	------	------	-----------	-----	----

Last Edited: 12/22/05
By: RBDMSadm

Form View

FLTR	DATE	NUM
------	------	-----