

3 023264

15-001-02432-00-00

To:

API NUMBER

20080002-019

STATE CORPORATION COMMISSION

sw sw se ne
SE, SW, NE 1/4

Sec/Twp/Rge S.23-T.26S-18E.

Wichita State Office Bldg. - PLUGGING SECTION

2885 feet from south section line

130 S. Market, Room 2078

1143 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well#

WEINER NO.BB-30

Operator License # 100101

County

ALLEN

Operator: STATE OF KANSAS

Well Total Depth

850' feet

Name & FEE FUND PLUGGING

Production Pipe: 2"

Size Feet 850'

Address

Surface Casing: 5 1/2"

Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐D & A ☐

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC.

Lic. #

30670

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 3:00 P.M. Day: 20 12 Month: 12 20 2007

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING CEMENTED IN 5 1/2" SURFACE CASING.

THE PLUGGING PROPOSAL WAS TO PERFORATE THE 2" CASING AND TO CIRCULATE

AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part ☐

TECHNICIAN

None ☐

Operations Completed: Hour: 5:00 P.M. Day: 20 12 Month: 12 20 2007

Actual Plugging Report: PROGRESS BELOW 275' WAS NOT POSSIBLE. THE WELL

WAS PERFOATED AT 270' AND AT 100'. 1" PIPE WAS RAN INTO THE WELL TO 275'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE

WELL AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM

SURFACE. 124 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: GPS SESSION POINT NO. WEI 19. (THIS WAS WELL NO. BB-30 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

RECEIVED

KANSAS CORPORATION COMMISSION

Clayton P. Titel
TECHNICIAN

FEB 04 2008

CONSERVATION DIVISION
WICHITA, KS