

3 023308

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER

15-001-02434-00-00

20080002-021

NE, SW, NE 1/4

Sec/Twp/Rge

S.23-T.26 S.-R 18 E

3323 feet from south section line

1132 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 100101Operator: STATE OF KANSASName & FEE FUND PLUGGING

Address

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC.

Lic. #

30670

Address: 19245 FORD RD., CHANUTE, KS. 66720Company to plug at: Hour: 11:00A.M. Day: 25 Month: 2 2008Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT MAYHAVE BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WASTO PERFORATE THE CASING SEVERAL TIMES AND TO CIRCULATE AS MUCH OF THEWELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

TECHNICIAN

None

Plugging attended by Agent: All ☒ Part ☐Operations Completed: Hour: 2:00P.M. Day: 25 Month: 2 2008Actual Plugging Report: THE 2" CASING WAS PERFORATED AT 200' AND AT 500'.1" PIPE WAS RAN INTO THE 2" CASING TO 840'. CEMENT WAS PUMPED INTO THE 1"PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPEWAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 123 SACKS OF CEMENTWERE PUMPED INTO THIS WELL.Remarks: GPS SESSION POINT NO. WEI 21. (THIS WAS WELL NO. BB-28 ON THE LEASE MAP.)(If additional description is necessary, use BACK of this form.)I DID observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION
Signed:
MAR 07 2008
CONSERVATION DIVISION
WICHITA, KS

Clayton P. Titel
TECHNICIAN

33749

6

289