

3 023280

15-001-02449-00-00

To:

API NUMBER

20080002-038

STATE CORPORATION COMMISSION

nense
SE, NE, NE 1/4

Sec/Twp/Rge S.23-T.26S-18E.

Wichita State Office Bldg. - PLUGGING SECTION

3777 feet from south section line

130 S. Market, Room 2078

203 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well#

WEINER NO.HH-26

Operator License # 100 101

County

ALLEN

Operator: STATE OF KANSAS

Well Total Depth 850' feet

Name & FEE FUND PLUGGING

Production Pipe: 2" Size Feet 850'

Address

Surface Casing: 8" Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC.

Lic. #

30670

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00 A.M. Day: 24 Month: 1 2008

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT MAY

HAVE BEEN CEMENTED IN AT T.D. ONLY. THE 2" AND 8" ANNULUS WAS OBSTRUCTED.

THE PLUGGING PROPOSAL WAS TO PERFORATE THE 2" CASING AND TO CIRCULATE

AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part ☐TECHNICIAN
None

Operations Completed: Hour: 12:00 P.M Day: 24 Month: 1 2008

Actual Plugging Report: THE 2" CASING WAS PERFORATED AT 200' AND AT 500'.

1" PIPE WAS RAN INTO THE 2" CASING TO 700'. CEMENT WAS PUMPED INTO THE 1"

PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE

WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 29 SACKS OF CEMENT

WERE PUMPED INTO THIS WELL.

Remarks: GPS SESSION POINT NO. WEI 38. (THIS WAS WELL NO. HH-26 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 03 2008

CONSERVATION DIVISION
WICHITA, KSClayton P. Titel
TECHNICIAN

PK