

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: State Of Kansas Fee FundName & Martin (Stich) Lease Project

Address _____

AB oil well XXXXXXX Gas Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, IncLic. # 3097Address: 19450 Ford Road, Chanute, Kansas 66720Company to plug at: _____ Hour: _____ Day: 21 Month: 12 2007Plugging proposal received from: Sam KepleyCompany Name: K-W Oil Well Service, Inc Phone: 620-433-7730Were: Wash well to TD and fill from btm to top with portland cement thru cement string.

Plugging Proposal Received by:

Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All _____ Part _____ None XXXXXXOperations Completed: Hour: _____ Day: 21 Month: 12 2007Actual Plugging Report: This location had to be dug up. It was 'marked' with a piece of 2" pipe.Mr. Kepley set 4' of 16" surface pipe. The drilling rig was moved to location and used to drill down to 240'thru cement. The drilling rig was moved from location. A one inch cement string was washed down to400 ft. The well was plugged from btm to top thru this cement string. A total of 104 sacks of portlandcement were used to plug well. The well was cut off below plow depth and the location restored.RECEIVED
KANSAS CORPORATION COMMISSIONRemarks: Control # 20080015-007(If additional description is necessary, use BACK of this form.)

MAR 21 2008

CONSERVATION DIVISION
WICHITA, KS

I did not observe this plugging.

Signed:

Alan M. Dunning
TECHNICIAN

2/27