

3 023164

15-207-02019-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License #

100

Operator: STATE OF KANSAS

Name &amp; FEE FUND PLUGGING

Address

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. #

30670

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00A.M. Day: 22 Month: 5 2007

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were: THIS WELL CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 1100' THAT HAD

BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO PERFORATE THE

4 1/2" CASING AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF

CEMENT INSIDE AND OUTSIDE THE 4 1/2' CASING.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All

Part

TECHNICIAN

None

X

Operations Completed: Hour:

4:00P.M.

Day:

22 Month:

5

2007

Actual Plugging Report:

THE 4 1/2" CASING WAS PERFORATED AT 700' AND AT

200". 1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 1100'. CEMENT WAS PUMPED INTO

THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 4 1/2" CASING AND FROM THE 4 1/2"

AND 8" ANNULUS AT SURFACE. THE 1" WAS REMOVED. DISPLACEMENT WAS FILLED

FROM SURFACE. 170 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (SPOT LOCATION ESTABLISHED BY GPS AS NO. MCG2)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel

RECEIVED  
TECHNICIAN KANSAS CORPORATION COMMISSION

JUN 18 2007

CONSERVATION DIVISION  
WICHITA, KS