

3 023161

15-207-02028-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License #

100

Operator: STATE OF KANSAS

Name &amp; FEE FUND PLUGGING

Address

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. #

30870

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00A.M. Day: 8 Month: 5 2007

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 1100' THAT HAD

BEEN CEMENTED IN AT T.D. ALSO, AVAILABLE INFORMATION INDICATED THAT THIS WELL

HAD BEEN PLUGGED BACK TO 650". THE PLUGGING PROPOSAL WAS TO FILL AS MUCH

OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All

Part

X

TECHNICIAN

None

Operations Completed: Hour: 12:00PM Day: 8 Month: 5 2007

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 650'. AT THAT

DEPTH SOLID CEMENT WAS ENCOUNTERED. CEMENT WAS PUMPED INTO THE 1" PIPE

UNTIL CEMENT CIRCULATED FROM THE 4 1/2" CASING AT SURFACE. 1" PIPE WAS RAN

INTO THE 4 1/2"&amp;12" ANNULUS TO 350'. AT THAT DEPTH SOLID CEMENT WAS ENCOUNTERED.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE ANNULUS

AT SURFACE. ALL 1" WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 259

SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (SPOT LOCTION ESTABLISHED BY GPS AS MCG 12) 13

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signature  
KANSAS CORPORATION COMMISSION

TECHNICIAN

MAY 21 2007

CONSERVATION DIVISION  
WICHITA, KS

PKT