


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-00326-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Ellis County. Sec. 25 Twp. 12S Rge. (E) 16 (W)



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Murfin Drilling Company
Lease Name Furthmeyer "B" Well No. 1
Office Address 617 Union Center, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 29 19 59
Application for plugging filed August 29 19 59
Application for plugging approved August 29 19 59
Plugging commenced August 29 19 59
Plugging completed August 29 19 59
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Petty, Nays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3441 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	213'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 400' with mud and sand.
Set 1st plug at 400'. Mixed and displaced 20 sxs. cement. Filled hole to 180'.
Set 2nd plug at 180'. Mixed and displaced 15 sxs. cement. Set top plug at 40'.
Displaced 1/2 sx. hulls and 10 sxs. cement.

RECEIVED
STATE CORPORATION COMMISSION
9-29-1959
SEP 29 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Murfin Drilling Company
Address 617 Union Center, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Murfin (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W R Murfin
617 Union Center, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of September, 19 59

My commission expires March 23, 1960
Donna M. Matzek Notary Public.




15-051-00326-00-00
WELL LOG

COMPANY Murfin Drilling Company
FARM Furthmeyer "B" NO. 1

SEC. 25 T. 12S R. 16W
LOC. NW NW NW

TOTAL DEPTH 3441'
COMM. 8-21-59 COMP. 8-29-59
SHOT OR TREATED
CONTRACTOR Murfin Drilling Company
ISSUED



CASING
20 10
15 8 5/8" @ 213' w/165 SXS.
12 6
13 5

ELEVATION 1878' K.B.
1873' G.L.
PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 213 Shale
- 440 Shale - Shells
- 490 Shale - Sand
- 600 Shale - Shells
- 660 Sand
- 1015 Red Bed -Shale -Shells
- 1056 Anhydrite
- 1795 Shale - Shells
- 3100 Lime - Shale
- 3373 Lime
- 3441 Lime & Shale

GEOLOGICAL TOPS:

- Topeka 2774
- Heebner 3051
- Toronto 3072
- Lansing-Kansas City 3102
- Base Kansas City 3342
- Conglomerate 3377
- Total Depth 3441

DST #1 3114-35
Open 30 min. Rec. 10'
mud. IF 0#. FF0#. BHP0#/20 min.

DST #2 3250-72
Open 30 min. Rec. 14' mud.
IF 0#. FF0#. BHP 0#/20 min.

RECEIVED
STATE CORPORATION COMMISSION
9-29-1959
SEP 29 1959
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas
County of Sedgwick ss:

I, W. R. Murfin of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Furthmeyer "B" #1 well.

Subscribed and sworn to before me this 25th day of September 19 59

My Commission Expires: March 23, 1960

W R Murfin

Donna M. Matzek
NOTARY PUBLIC
Donna M. Matzek