

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-00407-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Ellis County, Sec. 25 Twp. 12S Rge. 16 (E) W (W)

Location as "NE/CNW/SE/4" or footage from lines SE/4 NE/4 NE/4

Lease Owner R. P. Nixon, Oil Producer

Lease Name Thielen Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-20 19 56

Application for plugging filed 5-20 19 56

Application for plugging approved 5-20 19 56

Plugging commenced 5-20 19 56


Plugging completed 5-20 19 56

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3466 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 190'. Plug 1/2 sack hulls.

15 sacks cement through drill pipe.

Heavy mud to 40'. Plug @ 40'

1/2 sack hulls, 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mast Drilling, Inc.

Address P.O. Box 33, Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss. Contractor

James J. Thoman (employee-of-owner) or (owner-or-operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Mast Drilling, Inc.

(Signature) James J. Thoman Secy
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 31st day of May, 1956

My commission expires 8-9-58

Betty Dean Galbraith Notary Public.

PLUGGING
FILE SEC. 25 T. 12 R. 16 W
BOOK PAGE 65 LINE 4

RECEIVED
JUN 1 1956
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

15-051-00407-00-00

OPERATOR: R. P. Nixon, Oil Producer
Russell, Kansas

CONTRACTOR: Mast Drilling, Inc.
Russell, Kansas

LEASE: Thielen #1
SE/4 NE/4 NE/4
Sec. 25, T 12S, R 16W
Ellis County, Kansas

COMMENCED: 5-9-56
COMPLETED: 5-20-56

FORMATION	DEPTH
Rock & Sod	70
Rock	95
Shale & Shells	280
Shale	380
Sand	475
Shale	730
Shale & Red Bed	966
Anhydrite	1015
Shale & Shells	1310
Shale	1345
Shale & Lime	1415
Shale & Salt	1600
Lime & Shale	1772
Lime	1900
Lime & Shale	1970
Lime	2050
Lime & Shale	2235
Shale	2757
Sand	2770
Shale & Lime	2873
Lime	3246
Lime & Shale	3423
Conglomerate	3466
TOTAL DEPTH	3466

I hereby certify that the above is true and correct to the best of my knowledge.

Mast Drilling, Inc.

James K. Thomas
Secretary

STATE OF KANSAS)
)ss
COUNTY OF RUSSELL)

Subscribed and sworn to before me this 29th day of May, 1956,

Betty Jean Galyardt

My Commission expires 8-9-58

6-1-1956

PLUGGING			
FILE	SEC. 25	T. 12	R. 16W
BOOK	PAGE 65	LINE 4	