

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-051-19174-00-00
WELL PLUGGING RECORD

Ellis County, Sec. 31 Twp. 12 Rge. 16 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner Harms-Burt Drilling Company

Lease Name Brungardt Well No #1

Office Address

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 17 1955

Application for plugging filed " " 1955

Application for plugging approved " "(orally) 1955


Plugging commenced " " 1955

Plugging completed " " 1955

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3575 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|-----|--------|--------|------------|
| Surface | | 0 | 160 | 8 5/8" | 160 | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud from 3575' to 155'. Set plug at 155' with 15 sacks cement on top. Heavy mud to 40' with plug at 40' and 10 sacks cement on top of plug.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Harms-Burt Drilling Company
Address Box 184, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Allan Harms (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allan Harms
Box 184, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 9 day of Nov. 1955

My commission expires 1-20-58
Mary E Van Selt Notary Public.

PLUGGING
REC-31712-R/LHW
BOOK PAGE 2 LINE 15

11-10-1955
RECEIVED
CONSERVATION DIVISION
WICHITA, KANSAS

15-051-19174-00-00

DRILLERS LOG

Company: Harms-Burt Drilling Company

Farm: Brungardt #1 NE NE SW Sec. 31-12-16W, Ellis County, Kansas

Commenced: September 8, 1955

Completed: September 17, 1955

Elevation: 2039 KB

| | |
|-------------|----------------------|
| 0 - 20 | soil & clay |
| 20 - 160 | shale & shells |
| 160 - 615 | shale & shell w/clay |
| 615 - 750 | shale & red bed |
| 750 - 915 | sand |
| 915 - 1207 | shale & shells |
| 1207 - 1242 | Anhydrite |
| 1242 - 1925 | shale & shells |
| 1925 - 1960 | shale & lime |
| 1960 - 2190 | lime & shale |
| 2190 - 2245 | lime |
| 2245 - 2360 | lime & shale |
| 2360 - 2710 | shale & lime |
| 2710 - 3005 | lime & shale |
| 3005 - 3155 | lime |
| 3155 - 3277 | lime & shale |
| 3277 - 3515 | lime |
| 3515 - 3541 | lime & shale |
| 3541 - 3575 | Arbuckle lime |
| 3575 - | TD |

Set 160 feet of 8 5/8" surface pipe. Cemented with 125 sacks of common cement and 2 sacks of calcium chloride.

| | | |
|-------|--------------|------|
| Tops: | Anhydrite | 1207 |
| | Heebner | 3228 |
| | Toronto | 3254 |
| | Douglas | 3266 |
| | Lansing-K.C. | 3277 |
| | Arbuckle | 3541 |

Drill Stem tests:

| | | |
|-----|-----------|---|
| #1. | 3296-3329 | Open 45"-recovered 35' of mud with few specks of oil in top 5'. Shut in pressure 30# in 20 min. No FP's |
| #2 | 3543-3552 | Open 1 Hr.-rec. 100' salt wtr. Shut in Pressure 840# in 20 min. FP's 0 to 80#. |

Dry, plugged & abandoned.

AFFIDAVIT:

State of Kansas)
 SS
County of Barton)

I, Allan Harms, of Harms-Burt Drilling Company, being first duly sworn on oath state: I have knowledge of the facts, statements, and matters herein contained and the same are true and correct.

Subscribed and sworn to before me this 9 day of November 1955.

Allan Harms
Mary E Van Pelt
Notary Public

My commission expires 1-20-58.

PLUGGING 11-10-1955
31-12-16W
PAGE 2 LINE 15