

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-24,329

LEASE NAME Chrisler

15-051-24329-00-00

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2970 Ft. from S Section Line

2970 Ft. from E Section Line

LEASE OPERATOR Burnette Oil & Gas

SEC. 21 TWP. 12 RGE. 16 (E) or (W)

ADDRESS 1205 North "C" Street Wellington, KS 67125

COUNTY Ellis

PHONE# (316) 326-7312 OPERATORS LICENSE NO. 9560

Date Well Completed 10-9-85

Character of Well D&A

Plugging Commenced 10-9-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-9-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Ks.
to be filed by

Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3461'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 3430' w/25 sacks cement thru drill pipe

Next Plug: @ 1100' w/25

Next Plug: @ 600' w/100

Top Plug: @ 40' w/1 sack Hulls & 10 sacks cement 15 sacks in rat hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson

(Employee of Operator) or ~~XXXXXXXXXX~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 14 day of Oct, 1985

Deborah M. Dague

Notary Public

My Comm. STATE CORPORATION COMMISSION 4-29-86

RECEIVED

10-18-1985
OCT 18 1985

15-051-24329-00-00

DRILLER'S WELL LOG

DATE COMMENCED: October 2, 1985
DATE COMPLETED: October 9, 1985

Burnette Oil & Gas
CHRISLER #1
SE SE NW
Sec. 21, T12S, R16W
Ellis County, Ks.

ELEVATION: 1946 K.B.

0 - 730' Surface Soil, Shale, Sand
730 - 1084' Red Bed, Shale
1084 - 1127' Anhydrite
1127 - 2862' Lime & Shale
2862 - 3112' Lime
3112 - 3116' Shale
3116 - 3163' Lime & Shale
3163 - 3416' Lime
3416 - 3426' Shale & Lime
3426 - 3461' Dolomite
3461' RTD

FORMATION DATA

Anhydrite 1084'
Topeka 2862'
Keebner 3112'
Toronto 3139'
Kansas City 3163'
Base K.C. 3416'
Arbuckle 3426'
RTD 3461'

Surface Pipe: Set new 8-5/8"
23# pipe @ 517' w/225 sacks
60/40 pozmix 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 14 day of October, 1985.

My Comm. Expires:

4-29-86

Clarence M. Hague
Notary Public

Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
10-18-1985
OCT 18 1985

CONSERVATION DIVISION
Wichita, Kansas