

15-051-01202-00-00  
WELL PLUGGING RECORD

Ellis	County.	Sec. 29	Twp. 12S	Rge. 16	( <del>E</del> ) W	(W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SE SE NE						
Lease Owner H. H. BLAIR Et al						
Lease Name Dodge					Well No.	1
Office Address 600 Bitting Building, Wichita 2, Kansas						
Character of Well (completed as Oil, Gas or Dry Hole)					Dry	
Date well completed					August 30,	19 50
Application for plugging filed					September 15,	19 50
Application for plugging approved					September 16,	19 50
Plugging commenced					August 30,	19 50
Plugging completed					August 30,	19 50
Reason for abandonment of well or producing formation					Dry	

If a producing well is abandoned, date of last production..... 19.....  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced?..... Yes.....

OIL, GAS OR WATER RECORDS

### CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to .....feet for each plug set.

Filled the hole with mud to 134' - run 20 sacks cement; filled hole to 40' with mud. Put in rock bridge - run 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
9-28-1950  
SEP 28 1950  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to H. H. Blair  
Address 600 Bitting Building  
Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
L. E. Potucek (employee of owner) or (~~owner~~) of the above described well.

L. E. Potucek (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. H. Blair

600 Bitting Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of September, 1950

My commission expires July 3, 1954.

28-3273-S 4-50-10M

**PLUGGING**  
FILE SEC 29 T 18 R 16  
BOOK 28 LINE 15

15-051-01202-00-00

## DODGE #1 - WELL LOG

OWNED BY: H. H. BLAIR ET AL  
 COMMENCED: 8/ 3/50  
 COMPLETED: 8/30/50

LOCATION: SE SE NE  
 Sec. 29-12S-16W,  
 Ellis County, Kansas

CONTRACTOR: H. H. BLAIR  
 D & A  
 PRODUCTION:

ELEVATION:  
 2114 DF  
 2111 Or

## CASING RECORD:

Set 143' of 8 5/8" Surface Casing  
 cemented same with 100 Sacks Cement

Set 5 1/2" Casing at 3598', cemented  
 same with 50 Sacks Cement.

Lime Stone	75
Shale	300
Shale and Shells	485
Sand and Shale	580
Sand	610
Sand and Shale	800
Sand and Pyrite	840
Sand	910
Sand, Shale and Red Bed	1000
Shale and Pyrite	1030
Shale and Shells	1070
Red Bed, Shale and Shells	1300
Anhydrite	1340
Shale and Shells	1690
Salt and Shale	1875
Shale and Shells	2220
Shale and Lime	2280
Lime and Shale	2335
Lime	2435
Lime and Shale	2520
Shale and Shells	2790
Shale	2890
Lime and Shale	2910
Shale and Shells	2985
Sandy Shale	3030
Shale and Shells	3040
Shale and Lime	3080
Lime and Shale	3245
Shale and Lime	3303
Lime	3371
Lime and Shale	3393
Lime	3597
Arbuckle	3603
Rotary Total Depth	3603
Cable Tool - Log	

Dolomite 3606 - 3625  
 Cable Tool Total Depth 3625

RECEIVED  
 STATE COMMISSION  
 9-27-1950  
 SEP 27 1950  
 DONALD V. LEACH  
 Wichita, Kansas


STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I hereby certify that the above is a true and correct record of the  
 formations encountered in the drilling of the #1 Dodge, located in the SE SE NE  
 of Section 29-12S-16W, Ellis County, Kansas.

*Don E. Poterich*

Subscribed and sworn to before me this 5th day of September, 1950.

My commission expires: July 3, 1954



*Jay H. Leach*  
 Notary Public