


15-051-2013-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 29 Twp. 12S Rge. 16 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines NW SE SE
Lease Owner Sterling Drilling Company, et al
Lease Name Dickinson "A" Well No. 1
Office Address P. O. Box 129, Sterling, Kansas 67579
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 11, 19 67
Application for plugging filed December 11, 19 67
Application for plugging approved 19
Plugging commenced December 11, 19 67
Plugging completed December 11, 19 67
Reason for abandonment of well or producing formation
Dry Hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3565' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	2 1/2	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud, 100 sacks cement at 660'.
Plug #2 at 250' with 25 sacks cement. Top Plug at 40'
with 10 sacks cement. Cemented by Sun Cementing Company.

12-15-1967
DEC 15 1967

CONSERVATION DIVISION
PLUGGING RECORD

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS, COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner
F. A. Wuellner
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of December, 1967

BERNARD LAUDERMILK, Notary Public
My commission expires _____ Commission Expires January 22, 1970
Bernard Laudermilk
Bernard Laudermilk Notary Public.

STERLING DRILLING COMPANY
Sterling, Kansas 67579

WELL LOG ----- 15-051-20173-00-00 ----- -Dickinson A #1
Located: NW SE SE, Section 29-12S-16W, Ellis County, Kansas

OWNER: Sterling Drilling Company, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 2, 1967
COMPLETED: December 11, 1967

ROTARY TOTAL DEPTH: 3567'

LOG

0 - 260	Shale and Sand
260 - 430	Shale
430 - 960	Shale and Sand
960 - 1232	Shale, Shells, Red Bed
1232 - 1290	Anhydrite
1290 - 1550	Shale and Lime
1550 - 1925	Shale and Lime Streaks
1925 - 2293	Shale and Lime
2293 - 2400	Lime
2400 - 2585	Shale and Lime
2585 - 2693	Shale and Shells
2693 - 2910	Lime and Shale
2910 - 2990	Shale
2990 - 3540	Lime
3540 - 3567	Lime and Arbuckle

CASING RECORD

Ran 6 Jts. 8 5/8" 20# new seamless casing - 242.11 Pipe. Set at 254.11 K.B. Cemented with 160 sacks 50 x 50 Pozmix with 2% Gel and 2% HA5. Plug was down at 9:00 PM, 12-2-67 by Howco.

Plugged and Abandoned

12-15-1967
DEC 15 1967

DIVISION