

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
5-17-78  
MAY 17 1978  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Augustine of Murfin Drlg. has this

date requested permission to plug the following described well:

Mr. Augustine guarantees payment of the plugging fee.

Operator's full Name: Murfin Drlg. Co.

Complete Address: 617 Union Center, Wichita, Ks.

Lease Name: E. C. Casey Well No. 3

Location: C SW/4 Sec. 35 Twp. 10 Rge. (E)(W) 19

County: Riiks Total Depth 3550' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Augustine was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 600' thru drill

pipe. Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Messer  
Conservation Division Agent