

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
3-2-82  
MAR 2 1982

VERBAL PERMIT FORM  
(to be filed by Plugging Agent)  
Conservation Division  
Wichita, Kansas

Dear Sir:

Mr. L. A. Hartnett of Champlin Petroleum has this date requested permission to plug the following described well:

Operator's Full Name: Champlin Petroleum Company

Complete Address: Box 9365 - Ft. Worth, Tx. 76107

Lease Name: Sutor "A" Well No. 13

Location: NW 5W 5N Sec. 1 Twp. 10 Rge. 20 (E) (W)

County: Rooks Total Depth: 4037

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Hartnett was instructed to plug the well as follows:

8 5/8" @ 181' w/175 sk common - 5 1/2" @ 3954' w/400 sk common 1st stage - 250 sk Strata-Crete poz-mix 2nd stage - 400 sk 2% gel - 4% ca-cl. circ to surf. - hole in casing at 1859' - 2 7/8" tubing @ 1986' - Ordered 350 sk 5% pozmix 6% gel - 3% ca-cl, 12 sk shells - pumped in 50 sk cmt. and 12 shells - 150 sks, no pressure - Wait 2 hrs on cmt - pumped in add. 150 sk cmt - Wait 20 hrs. - Ordered 400 sk cmt, 6% gel 3% ca-cl, 2 lbs floccul per sk - pumped in 150 sk - pressure to 100 # P.S.I. wait 20 min - pressure to 400 # - pressure held - no vacuum check next day - cement to top of 5 1/2" pipe. (cmt. by Halliburton)

Dennis L. Hamel  
Conservation Division Agent