

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

RECEIVED
OCT 02 2003
10-02-03
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Tengasco Inc.
Address: P.O. Box 458; Hays, KS 67601
Phone: (785)625-6374 Operator License #: 32278
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 09-22-2003 (Date)
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing-KC Depth to Top: 3672 Bottom: 3696 T.D. 3790
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-163-02064
Lease Name: Croffoot "B"
Well Number: 9
Spot Location (QQQQ): _____ - SW _____ - NW _____ - SE
1650 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 11 Twp. 10 S. R. 20 East West
County: Rooks
Date Well Completed: 10-20-1956
Plugging Commenced: 9-29-2003
Plugging Completed: 9-29-2003

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing-KC	Oil / Water	3672	3696	8.625	223	None
				5.5	3775	None
** Perforated		3 holes at 2125', 1700', 975'.				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Ran 68 jts tbq (2100.49) spotted 25 sxs, 150#hulls, pulled 13 jts tbq to 1700, spotted 25 sxs, 150#hulls, pulled 28 jts tbq to 975, spotted 25sxs, 200#hulls, pulled 12 jts tbq to 450, pumped 75sxs, would not circ. pulled tbq out of hole pumped 160sxs down csg. let set four hours, had hard btm 100' dwn. Tied onto 8.625 pumped 50sxs, 250#hulls, max 50psi. All cmt was 60/40 poz 10% CC, total
Name of Plugging Contractor: _____ License #: _____ cmt 360sxs

Address: Allied Cementing
Russell, KS 67665

Name of Party Responsible for Plugging Fees: Tengasco Inc.

State of Kansas County, Ellis, ss.

Ed Glassman (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Ed Glassman
(Address) P.O. Box 458; Hays, KS 67601

SUBSCRIBED and SWORN TO before me this 30th day of September, 20 03

LINDA K. PFANNENSTIEL
NOTARY PUBLIC
STATE OF KANSAS
My Appl. Exp. 2/5/04

Linda K Pfannenstiel My Commission Expires: 2/5/04
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

ALLIED CEMENTING CO., INC.

15763

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>9/24/03</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>9:00 Am</u>	JOB START	JOB FINISH <u>NOON</u>
LEASE <u>Rowles</u>	WELL # <u>B-9</u>		LOCATION <u>206.6 4W 2S 10W 4 S</u>		COUNTY <u>Rock</u>	STATE <u>K</u>	
<u>OLD</u> OR NEW (Circle one)							

CONTRACTOR Express

TYPE OF JOB plug

HOLE SIZE _____ T.D. _____

CASING SIZE 53 DEPTH _____

TUBING SIZE 23 DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT AMOUNT ORDERED 360th 6440-10
500# Hull

COMMON _____ @ _____

POZMIX _____ @ _____

GEL _____ @ _____

CHLORIDE _____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

HANDLING _____ @ _____

MILEAGE _____ @ _____

EQUIPMENT

PUMP TRUCK CEMENTER Bar

366 HELPER Paul

BULK TRUCK

362 DRIVER Rufus

BULK TRUCK

_____ DRIVER _____

TOTAL _____

REMARKS:

Things @ 2125 spot 25 rbs w/
150" Hulls
pull to 1700 spot 25 rbs w/ 150" Hulls
pull to 800 spot 25 rbs w/ 200" Hulls
pull to 400 mix 13 rbs, pull things
mixed 100 rbs shut down
pump 50 rbs down now 200" shut in

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____

EXTRA FOOTAGE _____ @ _____

MILEAGE _____ @ _____

PLUG _____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

CHARGE TO Ten Gasco

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE [Signature]

PRINTED NAME _____

75
50
75
200