


15-163-03080-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County, Sec. 11 Twp. 10S Rge. (E) 20 (W)

Location as "NE/CNWxSWx" or footage from lines C S/2 NE NE

Lease Owner I. O. Miller

Lease Name Croffoot A Well No. 8

Office Address 619 Brown Building

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7/27/58 19

Application for plugging filed 7/27/58 19

Application for plugging approved 7/27/58 19

Plugging commenced 7/27/58 19

Plugging completed 7/27/58 19

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3844 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	249	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with drilling mud 3844 to 500 foot, set plug

W/20 sx. cement, filled hole to 240 feet with mud set plug

W/15 sx. cement, mud to 35 feet set plug W/cement to surface

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Earl F. Wakefield

Address 515 Union Center Building Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

F. G. Treutle (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. G. Treutle

619 Brown Bldg., Wichita, Kansas.

(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of August, 19 58

L. E. Warren

L. E. Warren Notary Public.

My commission expires Feb. 1, 1961

8-13-58
AUG 13 1958

PLUGGING
FILE SEC 11 T 10 R 20w
BOOK PAGE 120 LINE 8

CONSERVATION DIVISION
Wichita, Kansas

LEASE: Croffoot #8
OPERATOR: I. O. Miller
CONTRACTOR: Earl P. Wakefield
COMM: 7/20/58 COMP: 7/27/58

LOCATION: C S/2 NE NE
SECTION 11-10S-20W
Rooks County, Kansas
CASINO: 8 5/8" Set @ 249"

ELEVATION: 2231 D.F.

Soil	30
Sand	40
Shale and Shells	249
Shale and Lime Streaks	1170
Sand	1200
Shale	1668
Anhydrite	1720
Red Rock and Lime Streaks	1815
Shale/ Red Bed/ Anhydrite	1980
Shale/ Pyrite/ Lime	2130
Lime and Shale	2305
Shale and Lime	2460
Lime and Shale	2565
Lime	2722
Red Rock and Limestone	2762
Shale and Lime	2920
Lime and Shale	3020
Shale	3148
Lime and Shale	3204
Shale/ Oyp and Pyrite	3217
Shale/ Lime Streaks	3246
Lime W/ Shale Streaks	3318
Lime and Shale	3368
Lime	3395
Lime and Shale	3455
Heebner	3458
Lev. Lime	3463
Sny. Der.	3478
Toronto Lime	3481
Lime	3799
Red Shale and Lime	3837
Arb. Lime	3844
T.D.	3844

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log on the Croffoot #8 well, located C S/2 NE NE Section 11-10S-20W, Rooks County, Kansas

Earl P. Wakefield

By J. J. Boshell

Subscribed and Sworn before me this 9 day of August, 1958.

C. A. Snow
C. A. Snow Notary Public

My Commission expires July 26, 1962.

PLUGGING
FILE SEC. 11 T. 10 R. 20W
BOOK PAGE 120 LINE 8