

15-163-03081-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Rooks County, Sec. 11 Twp. 10 Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE 1/4 NW 1/4

Lease Owner I. O. Miller

Lease Name Croffoot C Well No. 3

Office Address P. O. Box 74, Ellis, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 13, 19 54

Application for plugging filed June 13, 19 54

Application for plugging approved June 13, 19 54

Plugging commenced 6 P.M. June 13, 19 54

Plugging completed 9 P.M. June 13, 19 54

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation None Depth to top Bottom Total Depth of Well 3865 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled to within 190' of top with heavy mud and bottom plug set. One-half sack of bulls put on top of plug, followed by 15 sacks of cement. Hole filled with heavy mud up to 40' from top and set top plug. 10 sacks of cement put above top plug.

RECEIVED
STATE CORPORATION COMMISSION
6-24-54

CONSERVATION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Virginia Drilling Company

Address 701 Brown Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Rooks, ss.

Paul W. Miller (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Miller Sup't.

(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of June, 1954

Eva M. Manion Notary Public.

My commission expires July 27, 1957

24-2675-5 2-52-20M

PLUGGING
FILE SEC 11 T 10 R 20W
BOOK PAGE 41 LINE 18

PAUL W. MILLER
 P. O. BOX 236
 PALCO, KANSAS
 July 7, 1954

T. A. Morgan, Director Conservation Division
 State Corporation Commission
 800 Bitting Building
 Wichita, Kansas

Well No.	3
Lease	Croffoot "C"
Description	SENWNW 11-10-20W
County, Rocks	
File No.	41-18

Dear Sir:

In response to the request contained in your letter of June 24th, the following is a well log of the above captioned dry hole:

Elevation	2250 DF	2253 RB
Topeka	3286	-1033
Heebner	3495	-1242
Tobonto	3518	-1265
Lansing-Kansas City	3532	-1279
Base Kansas City	3754	-1501
Conglomerata	3802	-1549
Simpson	3835	-1582
Arbuckle	3846	-1593
Total Depth	3865	

Yours very truly,

I. O. Miller

By *Paul W. Miller*
 Paul W. Miller, Sup't.

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 9 1954
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 11 T 10 R 20W
 BOOK PAGE 41 LINE 18