

15-163-03401-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County, Sec. 11 Twp. 10 Rge. 20 (E) (W)

Location as "NE/CNW&SW" or footage from lines NE NW NE

Lease Owner I. O. Miller

Lease Name Croffoot Well No. 1

Office Address Ellis, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole.

Date well completed 11-22-52 19

Application for plugging filed 11-22-52 19

Application for plugging approved 11-22-52 19

Plugging commenced 11-22-52 19

Plugging completed 11-22-52 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3825 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	210	8 5/8	214.70	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded to 200 ft. - set plug w/15 sx cement 1/2 sx hulls
Mudded to 40 ft - set plug w/ 10 sx. cement 1/2 sx hulls
to surface

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Virginia Drilling Co., Inc.

Address 701 Brown Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

S. A. Murphy (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. A. Murphy
701 Brown Bldg., Wichita 2, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of December, 1952

Mable Hawkins
Notary Public.

My commission expires Feb. 5, 1953.

24-2675-S 2-52-20M

PLUGGING
FILE SEC 11 T 10 R 202
BOOK PAGE 61 LINE 41

12-5-52
CONSERVATION DIVISION
Wichita, Kansas

Croffoot # 1 - NE NW NE Section 11-10-20 Rooks County, Kansas
Owner - I. O. Miller
Contractor - Virginia Drilg Co Inc
Commenced - Nov. 11, 1952
Completed - Nov. 22, 1952
Total depth - 3825
Elevation - 2220

Set 8 5/8" at 210 ft.

FORMATION	DEPTH
Sand & clay	0- 210
Sand - shale	210- 223
Blue shale	223- 650
Shale	650- 835
Sand- shale	835-1450
Sand - shells	1450-1630
Shale	1630-1678
Anhydrite	1678-1715
Shale	1715-1795
Shale-shells	1795-2197
Lime - shells	2197-2285
Broken lime	2285-2400
Lime-streaks shale	2400-2748
Lime-shells-shale	2748-2960
Shale - shells	2960-3115
Lime-shells-shale	3115-3340
Lime - shale	3340-3450
Lime	3450-3540
(Cherty at 3505)	
Lime-shale	3540-3604
Lime-white hard	3604-3640
Lime	3640-3712
Shale-lime shells	3712-3749
Lime-shale	3749-3780
Cherty-Conglomerate	3780-3825 PD

TOPS:
3456-Heebner
3477-Toronto
3493-Lansing KC
3712-Base KC
3777-Conglomerate

[Handwritten Signature]

Subscribed and sworn to before me, a Notary Public,
this 3rd day of December, 1952.

[Handwritten Signature]
Notary Public

My commission expires; Feb. 5, 1953

PLUGGING
FILE SEC. 4 T12 R22
BOOK PAGE 61 LINE 41

RECEIVED
STATE GEOLOGY COMMISSION
DEC 5 1952
GEOLOGICAL SURVEY DIVISION
Topeka, Kansas