


15-163-03248-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Rocks \_\_\_\_\_ County. Sec. 12 Twp. 10 Rge. 20 (E) 20 (W)  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW NW NE  
Lease Owner Sohio Petroleum Company  
Lease Name Desbien Well No. 7  
Office Address P.O. Box 673, Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 11-28 1952  
Application for plugging filed 12-1-52 After Verbal Approval 1952  
Application for plugging approved 11-28 1952  
Plugging commenced 11-29 1952  
Plugging completed 11-29 1952  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 385 1/2 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	1666	8-5/8"	1666	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud - Pushed bridge plug to 300' -  
Cemented through drill pipe w/15 sax - Mudded to 40' -  
Pushed another bridge to 40' - Placed 1/2 sack hulls on top - Cemented to surface with 10 sax cement -  
Plug 18' below ground level

12-1-52

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Trans-Era Drilling Co.  
Address W. Wichita Ave., Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
J. H. Bond (employee of owner) ~~CONTRACTOR~~ operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. H. Bond  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN to before me this 8th day of December, 1952  
W. Russell Miller  
Notary Public.

My commission expires July 2, 1953

**PLUGGING**  
FILE SEC 12 T 10 R 20  
BOOK PAGE 62 LINE 82

15-163-03248-0000

Yrahs Era Petroleum, Inc.  
Desbien #7

NW NW NE 12-10-20  
Hooks County, Kansas

Total Depth: 3854'  
Comm. 11/12/52  
Comp. 11/29/52

Casing

Cement

8 5/8" Set 1620'

846 sacks Pozmix

Formation	Depth
Surface soil-sand	40
Sand	97
Shale-shells	310
Shale-sand-sh-als	380
Shale	390
Shale-shells	1085
Sand	1110
Shale-shells	1140
Sand-shale	1390
Red bed	1425
Red bed-shale	1656
Anhydrite	1690
Red bed	1820
Shale-shells	2200
Shale-lime	2270
Sand-shale	2370
Shale-shells	2440
Shale-lime	2675
Lime	2732
Lime-shale	3437
Lime	3485
Lime-chert	3508
Lime	3706
Shale-chert	3787
Conglomerate	3823
Chert	3854'

STATE OF KANSAS )  
                          ) ss  
RUSSELL COUNTY )

I hereby certify that the above information is true and correct to the best of my knowledge.

-----  
*Cora Betty*  
-----

Subscribed and sworn to before me this 5th day of December, 1952.

-----  
*[Signature]*  
-----  
Notary Public

My commission expires: 6-17-54.

PLUGGING  
FILE SEC. 12-10-20  
BOOK PAGE 62, NO 32