

15-163-03526-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Rooks County, Sec. 12 Twp. 10 Rge. 20W (E) (W)  
2310' FNL 160' FWL

Location as "NE/CNW/SE/SW" or footage from lines  
Lease Owner Clinton Oil Company  
Lease Name C. Desbien #2 Well No. 5 RT KCC  
Office Address Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 1-12- 19 51  
Application for plugging filed 9-27 19 73  
Application for plugging approved 9-28 19 73  
Plugging commenced 10/29/73 19  
Plugging completed 11/1/73 19  
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production Feb. 19 63  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey  
Producing formation Topeka- Arbuckle Depth to top 3378' Bottom 3773' Total Depth of Well 3773 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	371	none
				7"	3771	819'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole, pushed plug to 3000' and ran 10' of sand and dumped 6 sacks cement. Loaded hole, shot pipe at 1501', 1193', 1003', 815', worked pipe loose and pulled 27 joints. Pumped 5 sacks hulls, 30 sacks gel and 140 sacks cement.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 20 1973

CONSERVATION DIVISION  
Wichita, Kansas

11-20-73

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
Address CHASE, KANSAS

STATE OF Kansas, COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of November, 1973

My commission expires

MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

Margaret Melcher  
Notary Public.

15-163-03526-0000480

W E L L L O G

CONTINENTAL OIL COMPANY

Described as your DESBIEN #2 Well,  
located in Rocks County, Kans.

FORMATION	FROM	TO
Sand & Shale	0	40
Shale & Sand	0	120
Shale	120	700
Shale & sand	700	1120
Sand	1120	1320
Shale	1320	1540
Anhydrite	1640	1678
Shale & shells	1678	1882
Broken Lime	1882	2365
Lime	2365	2436
Broken Lime	2436	2956
Lime & shale	2956	3332
Lime	3332	3691
Congl.	2691	3721
Congl. & Shale	3721	3769
Shale	3769	3774
Lime	3774	3776
Total Depth	3776	

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 26 1933  
CONSERVATION DIVISION  
Wichita, Kansas