

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-00300-0000
API NUMBER _____

LEASE NAME _____ C. Desbien _____

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER _____ #3 _____

440
~~996~~ ^{RTCC} Ft. from ^N Section Line

330 Ft. from ^W Section Line

LEASE OPERATOR _____ Hallwood Petroleum, Inc. _____

SEC. 12 TWP. 10S RGE. 20 (E) or (W)

ADDRESS _____ 4582 S. Ulster St. Parkway, Suite 1700, Denver, CO 80237 _____

COUNTY _____ Rooks _____

PHONE#(303) _____ 850-6257 _____ OPERATORS LICENSE NO. _____ 3613 _____

Date Well Completed _____ 7/31/51 _____

Character of Well _____ Oil _____

Plugging Commenced _____ 7/15/96 _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed _____ 7/16/96 _____

The plugging proposal was approved on _____ prior to plugging _____ (date)

by _____ Dennis Hammel _____ (KCC District Agent's Name)

Is ACO-1 filed? _____ Yes _____ If not, is well log attached? _____

Producing Formation _____ Lansing-Kansas City _____ Depth to Top _____ 3523' _____ Bottom _____ 3674' _____ T.D. _____ 3812' _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		-0-	341'	10 3/4	341'	-0-
		-0-	3700'	5 1/2	3770'	-0-
		-0-	3500'	2 3/8	3500'	3500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

RU L-K Wireline, perf 5 1/2 csg @ 2115', 1670-375', 2' each w/1 hole per ft, start tbg back, open end to 1100', finish running tbg to 3500', pmp 13 sks gel, 50 sks 60/40 Poz, 10% gel, 300# hulls, pull tbg 2100', pmp 75 sks 60/40 Poz, 10% gel, 300 hulls, circ cmt to surface, pulled tbg, hook up to 5 1/2 csg, pmp 45 sks dwn cmt 60/40 Poz, 10% gel, 200# hulls, press 800#, SI @ 500#, hook up to annulus, pmp 5 sks 60/40 Poz, 10% gel, press to 500#, SI. P&A. _____

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor _____ Allied Cementing, Inc. _____ License No. _____

Address _____ 24 S. Lincoln St., Russell, KS 67665 _____

RECEIVED
KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: _____ Hallwood Petroleum, Inc. _____

8-2-96
AUG 02 1996


STATE OF _____ Colorado _____ COUNTY OF _____ Denver _____

SS.
CORPORATION DIVISION
WICHITA, KS

_____ Nonya K. Durham _____ (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) _____ Nonya K. Durham _____

(Address) _____ 4582 S. Ulster St. Parkway, Ste 1700 _____
Denver, CO 80237 _____



Subscribed and sworn to before me this 30th day of _____ July _____, 19 96

_____ Judy E. Young _____
Judy E. Young, Notary Public

My Commission Expires: _____ 4/19/97 _____