


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Rooks County, Sec. 12 Twp. 10S Rge. 20W (E) (W)

Location as "NE/CNW/SE/SW" or footage from lines NW SE NW  
Lease Owner Clinton Oil Company  
Lease Name C. Desbien #6 Well No. \_\_\_\_\_  
Office Address Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 5-9-1952  
Application for plugging filed 9-27 19 73  
Application for plugging approved 9-28 19 73  
Plugging commenced 10/25/73 19 \_\_\_\_\_  
Plugging completed 11/ 1/73 19 \_\_\_\_\_  
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production Dec. 19 64  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey  
Producing formation Arbuckle O. H. Depth to top 3776' Bottom 3784' Total Depth of Well 3784 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 10-3/4	360	none
				5 1/2	3776	1007

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole, ran sand to 3750' and ran 5 sacks cement.  
Loaded hole, shot pipe at 1197', 1008', pulled 320 joints.  
Pumped 4 sacks hulls, 25 sacks gel and 120 sacks cement.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 20 1973

CONSERVATION DIVISION  
Wichita, Kansas

11-20-73

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) R. Darrell Kelso

CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of November, 19 73

Margaret Melcher  
Notary Public.

My commission expires



MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
Commission Expires  
Feb. 15, 1975

*W. J. Swenson*

15-163-03294-0000  
480

DRILLER'S LOG

Continental Oil Company  
#6 Desbien  
1650' from NL, 1650' from WL - 12-10S-20W  
Rooks County, Kansas

<u>FROM</u>	<u>TO</u>	
0	70	Clay & sand
70	200	Sand & shale
200	365	Sand, shale & shells
0	360	Reaming
365	815	Shale
815	970	Shale & sand streaks
970	1025	Shale
1025	1125	Shale & sand streaks
1125	1370	Sand
1370	1490	Red rock & shale
1490	1655	Red rock
1655	1700	Anhydrite
1700	2160	Shale & shells
2160	3495	Lime & shale
3495	3719	Lime
3719	3775	Cherty Congl.
3775	3784	Arb
	3784	Total Depth

COMMENCED: 4-19-52

COMPLETED: 4-30-52

CASING RECORD

Set 10-3/4" surface casing at 360' with 225 sacks of cement & 2 sacks calcium chloride, & 1% floeal  
Set 5-1/2" oil string at 3776' with 200 sacks of cement.

STATE OF KANSAS  
COUNTY OF SEDGWICK

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Continental Oil Company #6 Desbien, located 1650' from North Line, 1650' from West Line of Section 12-10S-20W, Rooks County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

By: *Leon L. Mehler*  
Leon L. Mehler

Subscribed and sworn to before me this 7th day of May, 1952.

*Wilma V. Shipman*  
Notary Public

My Commission Expires: May 24, 1952.



RECEIVED  
STATE CORPORATION COMMISSION  
SEP 28 1952  
CONSERVATION DIVISION  
Topeka, Kansas