

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-02087-0000

API NUMBER 156302087000

LEASE NAME Sutor 'B'

WELL NUMBER 7

2310 Ft. from S Section Line

3000 Ft. from E Section Line

SEC. 7 TWP. 10S RGE. 20W (E) or (W)

COUNTY Rooks

Date Well Completed 5-30-51

Plugging Commenced 12-4-85

Plugging Completed 12-4-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Sohio Petroleum Co.

ADDRESS 50 Penn Place, Suite 1100, Oklahoma City, OK 73118

PHONE# (405) 848-7571 OPERATORS LICENSE NO. 6854

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? (Dennis Hamel) Conservation Div, Wichita, Kansas

Is ACO-1 filed? No If not, is well log attached? No (log sent with Form CP-1)

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3762'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surface	308'	8 5/8"	308'	None
		Surface	3761'	5 1/2"	3761'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Perf @ 1115' and 950', three SPF cement down casing with 50 sks 60-40 poz w/10% gel and 1 sk hulls. Follow with 10sks gel cont. 1 sk hulls. Follow w/50 sks cement, 10 sks gel; 100 sks cmt. Max pressure 550 psi, ISIP-0. Tie onto allulus and pump 100 sks 60-40 poz w/10% gel and 1 sk hulls. Max pressure 100 psi, ISIP-0.
(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B. J. Titan License No. _____

Address Box 69, Hays, Kansas 67601

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Gary Plisga, Sohio Petroleum Company (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Gary Plisga

(Address) 50 Penn Place, Suite 1100

Oklahoma City, OK, 73118

SUBSCRIBED AND SWORN TO before me this 6th day of January, 19 86

Louise N. Skinner
Notary Public

My Commission Expires: March 13, 1989