

TATE OF KANSAS
TATE CORPORATION COMMISSION
30 S. Market, Room 2070
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-163-02085-00-01

LEASE NAME Sutor B

WELL NUMBER 55

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1650 Ft. from S Section Line

4290 Ft. from E. Section Line

SEC. 12 TWP. 10S RGE. 20W (E) or (W)

COUNTY Rooks

Date Well Completed _____

Plugging Commenced 2-5-01

Plugging Completed 2-6-01

LEASE OPERATOR VESS OIL CORPORATION

ADDRESS 8100 E. 22nd. N. #300 Wichita, Kansas 67226

PHONE(S) (316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well Inj. E 20403.1

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3766-1/2'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out <u>2-22-01</u>
				<u>8-5/8"</u>	<u>1615'</u>	<u>None</u>
				<u>5-1/2"</u>	<u>3763-1/2'</u>	<u>2500'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each sk. Plug ged off bottom with sand to 3500' and 5 sks. cement. Shot pipe @2500' pulled up to 2150, pumped 150 sks. cement w/300# Hulls, pulled up to 1650', pumped 40 sks. cement w/100# hulls, pulled up to 950', pumped 40 sks. cement w/100# hulls, pulled up 200' and circulated 45 sks. cement, 60/40 pos, 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact
statements, and matters herein contained and the log of the above-described well as filed in
the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 20th day of February 2001.

[Signature]
Notary Public

My Commission Expires: _____



Form CP
Revised 05-