

TATE OF KANSAS  
TATE CORPORATION COMMISSION  
30 S. Market, Room 2070  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

API NUMBER 15-163-02084-00-01

LEASE NAME Sutor B

WELL NUMBER 4

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2310 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 12 TWP. 10 RGE. 20W (E) or (W)

COUNTY Rooks

LEASE OPERATOR VESS OIL CORPORATION

ADDRESS \*) E. 22nd. N. #300 Wichita, Kansas 67226

PHONE (316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed \_\_\_\_\_

Plugging Commenced 2-7-01

Plugging Completed 2-13-01

The plugging proposal was approved on \_\_\_\_\_ (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3742'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD 2-22-01

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	1630'	None
				5-1/2"	3738'	2520'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each. Plugged off bottom with sand to 3500' and 5 sks. cement. Shot pipe @2520', pulled up to 2150', pumped 150 sks. cement w/300# hulls, pulled up to 1650', pumped 40 sks. cement w/100# hulls, pulled up to 950', pumped 40 sks. cement w/100# hulls, pulled up to 200' and circulated 45 sks. cement. 60/40 pos. 10% Gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact  
statements, and matters herein contained and the log of the above-described well as filed to  
the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 20th day of February, 2001.

James Strubberg  
Notary Public

My Commission Expires: \_\_\_\_\_

