


15-163-03525-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17037
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Rooks County, Sec. 12 Twp. 10 Rge. 20 (WE) (W)
Location NE/CNWSW or footage from lines SE SE NW
Lease Owner Clinton Oil Company
Lease Name C. Desbien #1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Dec 14 19 59
Application for plugging filed 9-27 19 73
Application for plugging approved 9-28 19 73
Plugging commenced 10/31/73 19
Plugging completed 11/1/73 19
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production July 19 73
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locals well covered on above Section Plat

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation L/KC Depth to top 3584' Bottom 3741' Total Depth of Well 3743 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	358	none
				7"	3740	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, set sand bridge at 3518', dumped 6 sacks cement. Pipe was squeezed, set rock bridge at 690' and pumped 25 sacks cement on top of bridge and 5 sacks mud, set rock bridge and pumped 25 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
NOV 20 1973
CONSERVATION DIVISION
Wichita, Kansas
11-20-73

(If additional description is necessary, use BACK of this sheet.)
Name of Plugging Contractor KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso

CHASE, KANSAS

Subscribed and sworn to before me this 5th day of November 19 73

Margaret Melcher
Notary Public

My commission expires

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

15-163-03825-0000

W E L L L O G

CONTINENTAL OIL COMPANY

Described as your ~~DESBIEN #1~~
Well, located in Section 12,
Township 10 South, Range 20
West, Rooks County, Kansas

FORMATION	FROM	TO
Shale & sand	0	200
Shale	200	360
Shale	360	1300
Shale & sand	1300	1440
Red Bed	1440	1618
Anhydrite	1618	1665
Shale & shells	1665	2187
Broken Lime	2187	2520
Lime	2520	2790
Broken Lime	2790	2883
Lime	2883	2970
Broken Lime	2970	2975
Lime & shale	2975	3145
Broken Lime	3145	3215
Lime & shale	3215	3329
Lime	3329	3697
Congl. & chert	3697	3720
Shale	3720	3739
Lime	3739	3744
Total Depth	3744	

RECEIVED
STATE CORPORATION COMMISSION
SEP 28 1973
CONSERVATION DIVISION
Wichita, Kansas