

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 500 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-163-03295-0000

LEASE NAME Desbien

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER #5

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 12 TWP. 10 RGE. 20 (E) or (W)

COUNTY Rooks

Date Well Completed 9/19/51

Plugging Commenced 12/27/89

Plugging Completed 12/29/89

LEASE OPERATOR BP Exploration

ADDRESS 9401 SW Fwy, Houston, TX 77074

PHONE# (713) 272-5000 OPERATORS LICENSE NO. 06854

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on December 21, 1989 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3771 Bottom NDE T.D. 3827

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing	Oil (3479-3771)	0	346	8 5/8"	346	5'
Arbuckle	Oil (3771-NDE)	0	3774'	5 1/2"	3774'	5'
		3766	3822	3 1/2"	56'	0'

01-19-90  
 RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 19 1990  
 CONSERVATION DIVISION  
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Set EZSV @ 1750' Pumped 185sx cmt below. Stung out & circ 116 sx cmt to surface. Shot two holes @ 950' tied onto 5 1/2" & pumped 15 sx cmt down hole. Tied onto 5 1/2" x \* 5/8" annulus & pumped 100 sx cmt down annulus. Cut well head 5' below surface & welded cap on. Cement was 65/35POZ w/ 8% gel & 2% CaCl  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287

Address 1100 E. 8th, Hays, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: BP Exploration

STATE OF Texas COUNTY OF Harris, ss.

Scott Marshall (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott Marshall

(Address) 9401 SW Fwy, Houston, TX 77074

HILDA I. GOODMAN  
 Notary Public  
 STATE OF TEXAS  
 My Comm. Exp. Jan. 13, 1992  
 My Commission Expires 1-18-92

AND SWORN TO before me this 17th day of January, 19 90  
Hilda I. Goodman  
 Notary Public