

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

WELL PLUGGING RECORD  
K.A.R. -82-3-117

API NUMBER 15-163-22,502 -0001

LEASE NAME Desbien

WELL NUMBER #9

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

1605 ~~4595~~ ~~3615~~

Ft. from S Section Line  
Ft. from E Section Line

LEASE OPERATOR VESS OIL CORPORATION

SEC. 12 TWP. 10S RGE. 20W (E) or (W)

ADDRESS 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226

COUNTY Rooks

PHONE # (316) 682-1537 OPERATOR'S LICENSE NO. 5030

Date Well Completed 8/23/85

Character of Well oil

Plugging Commenced 3/27/01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4/6/01

The plugging proposal was approved on 3/30/01; verbal approval - prior \_\_\_\_\_ (date)  
by David Williams \_\_\_\_\_ (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation LKC Depth to Top 3470' Bottom 3682' T.D. 4133'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	282'	-----
				5-1/2"	3865'	-----
				DV	1493'	-----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Plugged and abandoned as follows: TIH w/2 7/8" workstring to 3600'. Tied onto braden head and pumped 15 sx cement -

500#. Spotted down tbg w/50 sx cement w/400# hulls. Pull tbg to 3000' and spotted 15 sx gel. Pulled tbg to 1800'.

Spotted 125 sx cement w/no cement to surface. TOH to 300'. Pumped 35 sx cement w/no cement to surface.

TOH w/tbg. Tbg showed cement at 90' FS. Will top off later. 4/6/01 - Topped off w/cement, cut off and capped.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc.

RECEIVED  
LICENSE NO. 4-24-01  
3 24 2001

Address P.O. Box 31- Russell, KS 67665-0031

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

W.R. Horgan (Employee of Operator) or (Operator) of  
above-described well, being first duly sworn on oath, says that: That I have knowledge of the facts,  
statements and matters herein contained and the log of the above-described well as filed that  
the same are true and correct, so help me God.

(Signature)

W.R. Horgan  
8100 E. 22nd St. N., Bldg. 300  
Wichita, KS 67226

(Address)

SUBSCRIBED AND SWORN TO before me this 19TH day of April 2001

My Commission Expires:

MICHELLE D. HENNING  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 11/01/01

Notary Public

Form CP-4  
Revised 05-88

OR

# ALLIED CEMENTING CO., INC.

15-163-22502-0001

6713

TO P.O. BOX 31  
RUSSELL, KANSAS 67665

*CEMENTING  
TICKET  
FOR PUMP  
JOB*

SERVICE POINT:

*Russell*

DATE <i>3-27-41</i>	SEC.	TWP.	RANGE	CALLED OUT <i>10:00 AM</i>	ON LOCATION <i>11:30 AM</i>	JOB START	JOB FINISH <i>2:45 PM</i>
LEASE <i>Desbien</i>	WELL # <i>9</i>	LOCATION <i>Zurich 36 1 1/2</i>			COUNTY <i>X 006</i>	STATE <i>K</i>	
( ) OLD OR NEW (Circle one)							

CONTRACTOR *Spickard H. H.*

TYPE OF JOB *plus*

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_

CASING SIZE *5-2* \_\_\_\_\_ DEPTH \_\_\_\_\_

TUBING SIZE *2-3/8* \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

OWNER \_\_\_\_\_

CEMENT AMOUNT ORDERED

*225 sk of 6/40 10*

*529 HLL*

COMMON	<i>535</i>	@	<i>6.35</i>	<i>857.25</i>
POZMIX	<i>90</i>	@	<i>3.45</i>	<i>292.50</i>
GEL	<i>30</i>	@	<i>9.50</i>	<i>285.00</i>
CHLORIDE		@		
<i>Hulls</i>	<i>5</i>	@	<i>18.00</i>	<i>90.00</i>
		@		
		@		
		@		
		@		
		@		
HANDLING	<i>26.00</i>	@	<i>1.05</i>	<i>273.00</i>
MILEAGE	<i>44/sk</i>	@	<i>1/mile</i>	<i>345.20</i>
TOTAL				<i>2192.95</i>

EQUIPMENT

PUMP TRUCK # *177* CEMENTER *Bill* HELPER *L. W.*

BULK TRUCK # *211* DRIVER *W. H. C.*

BULK TRUCK # \_\_\_\_\_ DRIVER \_\_\_\_\_

REMARKS:

*Logging @ 35.50 spot 50 sk  
4 300' # Hulls pull to 3000  
Spot 150 sk pull to 1800'  
Cement w 125 sk w/ 200 # Hulls  
pull to 300' Cement 35 sk*

SERVICE

DEPTH OF JOB \_\_\_\_\_

PUMP TRUCK CHARGE \_\_\_\_\_ *450.00*

EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_

MILEAGE *38* @ *3.00* *114.00*

PLUG \_\_\_\_\_ @ \_\_\_\_\_

TOTAL *564.00*

CHARGE TO: *Russell J*

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

FLOAT EQUIPMENT

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

TOTAL \_\_\_\_\_

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE *John H. H.*

TAX \_\_\_\_\_

TOTAL CHARGE *2756.95*

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

PRINTED NAME