

15-051-19242-00-00

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

STATE CORPORATION COMMISSION
3-20-1961
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: SW SW SW Sec. 12 Twp. 12 Rge. 16 (E) (W)

Name of Field: _____ Total Depth: 3327

I have this date completed supervision of plugging of:

Lease Name: Dreiling Well No. C-1

Operator's Full Name: Leo J. Dreiling

Complete Address: Victoria, Kansas

Plugging Contractor: Ace Pipe Pulling Co

Address: Great Bend, Kansas License No. 2

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 3PM Day 13 Month 3 Year 61

The above well was plugged as follows:

10 3/4" 115' circulated with cement - 7" 3327' with 150 sax cement. PB to 3260' - perforated 2750'.

Sand to 2720', set 4 sax cement with dump bailer, pulled 2390' 7" to 300', circulated hole with heavy mud through 7" at 300' (19 sax Gel), displaced 20 sax cement through 7" at 300', heavy mud to 125', displaced 20 sax cement through 7" at 125', heavy mud to 25' set bridge and cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: *Leson Petty*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

INVOICED
DATE 4/5/61
INV. NO. 2888-w