

STATE CORPORATION COMMISSION  
15-051-19243-00-00  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
7-23-1974  
JUL 23 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Dreiling Oil, Inc.

Complete Address Route #2, Victoria, Kansas 67671

Lease Name Dreiling "C" Well No. 2

Location SE SW SW Sec. 12 Twp. 12 Rge. (E) (W) 16

County Ellis Total Depth 3660'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 9:30 A Day 20 Month 7 Year 1974

The above well was plugged as follows:

- Total Depth 3660' 8 5/8 csg set at 100' cwc 85 sk.
- 5 1/2 csg set at 3492' cw 100 sk cmt.
- 5 1/2 csg PBTD 3492' with top perf. (2959'.
- DV tool set at 993' cwc to surface. No pipe recovered.
- Set 5 1/2 wood plug at 2900' -poured 50' sand -dumped 3' sk' com with dump bailer.
- Filled 5 1/2 csg with mud to 500' -set rock & sand bridge & filled with readymix cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: L. J. Mansley  
Well Plugging Supervisor

DATE 7/23/74  
INV. NO. 9571-W