

15-051-04358-00-00

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
3-13-1961  
CONSERVATION DIVISION  
WICHITA, KANSAS

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis  
Location: CS 1/2 NE SE Sec. 15 Twp. 12 Rge. 16 (E) (W) \_\_\_\_\_  
Name of Field: \_\_\_\_\_ Total Depth: 3409

I have this date completed supervision of plugging of:

Lease Name: Dickinson Well No. C-1

Operator's Full Name: Leo J. Dreiling

Complete Address: Victoria, Kansas

Plugging Contractor: Ace Pipe Pulling Co

Address: Great Bend, Kansas License No. 2

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 3PM Day 8 Month 3 Year 61

The above well was plugged as follows:

8 5/8" 125 circulated with cement - 5 1/2" 3400' with 75 sax cement.  
Filled with sand to 3390', set 4 sax cement with dump bailer, pulled  
2985' 5 1/2" to 300', circulated hole with heavy mud through 5 1/2" at 300',  
displaced 20 sax cement through 5 1/2" at 300', heavy mud to 150', displaced  
20 sax cement through 5 1/2" at 150', heavy mud to 35', set bridge and 10 sax  
cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: *Edwin Letey*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor

Remarks:

INVOICED  
DATE 3/14/61  
INV. NO. 2796-W