

15-051-20812-00-00

KANSAS

Form CP-3

Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-9-1973
JUL 9 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil, Inc.

Complete Address R. R. # 2 Victoria, Kansas 67671

Lease Name Froelich Well No. 1

Location C E/2 NE NW Sec. 15 Twp. 12 Rge. (E) (W) 16

County Ellis Total Depth 3368'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling

Address Box 1082 Great Bend, Kansas 67530 License No. 623

Operation Completed: Hour 10:15 A Day 6 Month 7 Year 1973

The above well was plugged as follows:

Total Depth 3368' 8 5/8 csg set at 198' cwr

4 1/2 csg set at 3362' cw 125 sk.

Filled 4 1/2 csg W/sd (3340-3368) Dumped 3 sk cmt W/dump bailer. (3315-3340)

Cutoff and recovered 2510' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released 8 5/8 plug and

pumped 130 sk 50-50 poz cmt W/4% added gel by Sun Cementing Co. PP Max. 500 lbs.

SIPres. 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 7/10/73

INV. NO. 7615-W