

15-051-22613-00-00

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22,613

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Dreiling L. T. D. of Colorado

Complete Address 410-17th St., Suite #1140, Denver, Colorado 80202

Lease Name Dickinson Well No. #2-15

Location NW SE NW Sec. 15 Twp. 12 Rge. 16 (East) (West)

County Ellis Total Depth 3441'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor C & R Drilling Company

Address 410-17th St., Suite #1140, Denver, Colo. 80202 License No. \_\_\_\_\_

Operation Completed: Hour: 4:00AM Day: 20th Month: Jan. Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8"-197' s.p. cuc. w/110 sacks common-2% Gel.-3% Cal. Cl.

Ordered 135 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 660' w/70 sacks cement

2nd plug @ 200' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate 10 sacks of cement in rat hole and 5sacks of cement in mouse hole.

Amount of Surface Casing: 197' of 8 5/8".

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Rotary crew phoned me the plugging time at 8:15AM and informed me they had plugged at 4:00AM this date.

Signed: [Signature]  
Conservation Division Agent

2-3-82  
9186-6  
RECEIVED  
CONSERVATION COMMISSION  
1-25-1982  
JAN 25 1982