

15-163-01145-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

ROOKS County. Sec. 5 Twp. 10S Rge. (E) 20 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW SW

Lease Owner SINCLAIR OIL & GAS COMPANY

Lease Name W. E. Baldwin Well No. 8

Office Address Box 521, Tulsa 2, OKLAHOMA

Character of Well (completed as Oil, Gas or Dry Hole) DRY COMPLETION

Date well completed June 1, 19 53

Application for plugging filed June 9, 19 53

Application for plugging approved June 8, 19 53

Plugging commenced June 1, 19 53


Plugging completed June 1, 19 53

Reason for abandonment of well or producing formation Dry Completion

If a producing well is abandoned, date of last production Dry Completion 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - (Verbal)

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Hays, Kansas

Producing formation Arbuckle not located in conglomerate at completion Depth to top Bottom Total Depth of Well 3945 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Blue Shale				10-3/4" OD	208'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rotary Mud 3945 - 200'
20-Sacks Cement 200 - 40'
~~10-Sacks~~
Sacks Cement
& 1/2-Sack Hulls 40' - 0
10-3/4" Surface Casing Capped

CERTIFIED COPY OF WELL LOG ATTACHED

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mr. W. B. Rhees
Address Box 551, Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
I, W. B. RHEES (employee of owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Box 551, Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18 day of July, 19 53

My commission expires April 24 1956

PLUGGING
FILE SEC 5 T 10 R 20W
BOOK PAGE 106 LINES 35

23-5091-s 8-50-10M

RECEIVED
STATE CORPORATION COMMISSION
7-20-53
JUL 20 1953
Notary Public.

CONSERVATION DIVISION
Wichita, Kansas

Company: Sinclair Oil & Gas Company
 Contractor: Glenn R. Nye Drilling Company
 Commenced: May 17, 1953
 Completed: June 1, 1953

Farm: W.E. Baldwin #8
 Location: SW¹/₄ Sec. 5-10-20,
 Rooks County, Kansas
 Casing Record: 13" set at 208'
 Dry & Abandoned

(figures below indicate bottoms)

cement	208
shale	520
shale & sand	600
shale & sand	755
sand & gumbo	900
sand	1030
shale & sand	1275
sand	1470
shale & red bed	1585
shale & red bed	1775
anhydrite	1810
shale & red bed	1940
shale & red bed	2220
shale & lime	2350
shale & lime	2460
lime & shale	2560
lime & shale	2645
lime & shale	2715
lime & shale	2815
lime & shale	2915
lime & shale	2995
lime & shale	3070
shale	3150
shale & lime	3210
lime & shale	3290
lime & shale	3325
lime & shale	3360
lime	3420
lime	3460
lime & shale	3495
lime	3510
lime	3580
lime	3615
lime	3647
lime	3665
lime	3710
lime	3740
lime	3765
lime	3800
lime	3830
conglomerate	3845
conglomerate cherty	3857
conglomerate	3863
conglomerate	3874
conglomerate	3925
conglomerate	3945

Heebner 3509'
 Kansas City 3550'

T.D.

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

PLUGGING
 FILE SEC 5-10-20W1
 BOOK PAGE 106 LINE 35

GLENN R. NYE DRILLING COMPANY

BY Claude N. Bard

STATE OF KANSAS)
) SS
 Rooks COUNTY)

RECEIVED
 NOTARY PUBLIC DIVISION

Subscribed to and sworn to before me, a notary public, in and for said County and State this 5th day of June, 1953

John L. Spivey
 Notary Public

My Commission Expires May 9, 1957