

#4

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-23,210-0000

LEASE NAME McKenna

WELL NUMBER 1

4620 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 7 TWP. 10S RGE. 20 (E/W)(N/S)

COUNTY Rooks

Date Well Completed 9/11/92

Plugging Commenced 9/11/92

Plugging Completed 9/11/92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR West Central Oil

ADDRESS 229 S. Franklin, Russell, KS 67665

PHONE#(913) -483-2585 OPERATORS LICENSE NO. 30678

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/11/92 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3877'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	220'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Mud laden fluid 3877'-3847' 40 sks cement @ 250'

20 sks cement @ 3847' 10 sks cement @ 40'

20 sks cement @ 1800' 15 sks in rathole

100 sks cement @ 1000'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: West Central Oil

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or _____ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.

(Signature) [Signature]
Kyle B. Branum
(Address) Box 506, Russell, KS 67665-0506

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1992
WICHITA, KANSAS
CONSERVATION DIVISION

SUBSCRIBED AND SWORN TO before me this 14th day of Sept., 19 92

GLEND A. R. TIFFIN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 2-6-96

[Signature]
Glenda R. Tiffin, Notary Public

Commission Expires: 2-6-96

15-163-23210 - 0000

EMPHASIS OIL OPERATIONS

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: West Central Oil
229 S. Franklin
Russell, KS 67665

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: McKenna

WELL #1

LOCATION: C NW NE
Section 7-10S-20W
Rooks County, Kansas

LOGGERS TOTAL DEPTH: 3855'

ROTARY TOTAL DEPTH: 3877'

COMMENCED: 9/4/92

CASING: 8-5/8" @ 220' w/150 sks cement

ELEVATION: 2259' K.B.

COMPLETED: 9/11/92

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Cedar Hills	1230'	Toronto	3522'
Shale	1380'	Lansing-Kansas City	3540'
Anhydrite	1772'	Base Kansas City	3765'
Shale	1805'	Arbuckle	3847'
Topeka	3297'	R.T.D.	3877'
Heebner	3499'		


STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Kyle B. Branum

Subscribed and sworn to before me on August 14, 1992.

My commission expires: February 6, 1996.




Glenda R. Tiffin, Notary Public
RECEIVED
STATE CORPORATION COMMISSION
SEP 1 5 1992
RECEIVED
CONSERVATION DIVISION
STATE CORPORATION COMMISSION
SEP 16 1992
CONSERVATION DIVISION
Wichita, Kansas