

WELL PLUGGING RECORD

Rooks County, Sec. 7 Twp. 10 Rge. 20 (E) W. (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW $\frac{1}{4}$ NE $\frac{1}{4}$ SW $\frac{1}{4}$
Lease Owner Republic Natural Gas Company
Lease Name Temple Well No. 2
Office Address Box 126, Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed January 10 1952
Application for plugging filed January 16 1952
Application for plugging approved Verbal approval from Eldon Petty 1-9-52
Plugging commenced January 10 1952
Plugging completed January 15 1952
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production..... 19.....
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top 3872' Bottom Total Depth of Well 3947' Feet
Show depth and thickness of all water, oil and gas formations.

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

3947 to 196	Heavy rotary mud
196 to 136	Cement, 35 sacks
136 to 75	Heavy rotary mud
75 to Surface	Cement, 25 sacks

Top plug did not hold and settled to depth of 115'.
On 1-15-52 hole was recemented using 60 sacks of cement, cementing from 115' to surface.
Globe Cementing Company was used on both operations.

1-17-52

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor..... Jones, Shelburne & Farmer, Inc.

Address..... Russell, Kansas

STATE OF Kansas COUNTY OF Barton ss

Paul Horst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 126, Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of January 1952

My commission expires.....8-20-55

6-51—20M

-20-55
 23-8390
 FBI REC 7-11-60
 BOOK PAGE 138 LINE 10

DRILLING LOG

Company: Republic Natural Gas Company
 Lease: Temple
 Well No: 2
 Contractor: Jones, Shelburne & Farmer
 Commenced: 12-20-51
 Completed: 1-15-52
 Location: SW/4 NE/4 SW/4 Section 7-10-20, Rooks County, Kansas

0 - 198	Shale and sand
198 - 365	Shale
365 - 800	Shale and sand
800 - 1325	Shale and shells
1325 - 1730	Red bed and shale
1730 - 1785	Anhydrite
1785 - 1950	Shale and shells
1950 - 2200	Shale
2200 - 2325	Shale and lime
2325 - 2525	Lime and shale
2525 - 2630	Shale and lime
2630 - 2675	Lime
2675 - 2905	Lime and shale
2905 - 2955	Shale and lime
2955 - 3050	Lime and shale
3050 - 3190	Shale and lime
3190 - 3275	Lime and shale
3275 - 3405	Shale and lime
3405 - 3605	Lime and shale
3625 - 3710	Lime
3710 - 3765	Lime and shale
3765 - 3805	Chert
3805 - 3829	Chert & lime
3829 - 3845	Cherty conglomerate
3845 - 3848	Conglomerate
3848 - 3947	Lime
3947	T.D.

