


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 15 Twp. 12 Rge. 17 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SW SW NW
Lease Owner C-G DRILLING CO. & OIL TRADING ASSOC.
Lease Name Herman Well No. 1
Office Address 107 Rule Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 27 1955
Application for plugging filed September 26 1955
Application for plugging approved September 26 1955
Plugging commenced September 27 1955
Plugging completed September 27 1955
Reason for abandonment of well or producing formation Too low Structurally

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3773 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	188'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 180'. Set plug.
Put in 1/2 sack Hulls and 15 sacks of cement.
Filled with heavy mud up to 40'. Set plug.
Filled to top with 1/2 sack Hulls and 10 sacks cement.

10-1-1955

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G DRILLING CO.
Address 107 Rule Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
JAY H. GALLOWAY (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jay H. Galloway
107 Rule Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 1955

My commission expires May 20, 1959 Vicky Jacobs Notary Public.

PLUGGING
FILE SEC 15 T 12 R 17
BOOK PAGE 4 LINE 40

19267
 15-051-~~21050~~-00-00
 CONTRACTOR'S WELL LOG

OPERATOR C-G DRILLING CO. & OIL TRADING ASSOC. WELL NAME HERMAN #1

WELL LOCATION SW SW NW 12-12S-17W DIG #0

COUNTY ELLIIS STATE KANSAS

COMMENCEMENT DATE SEPTEMBER 14, 1955 COMPLETION DATE SEPTEMBER 27, 1955

LOG OF WELL

Elevation 2137 rotary bushing.
 All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	187	Sand-Shale		
187	330	Shale		
330	725	Shale-Shells		
725	775	Pyrite-Sand		
775	995	Sand-Shale		
995	1363	Shale-Red bed		
1363	1392	Anhydrite		
1392	1915	Shale-Shells		
1915	2050	Shale-Lime		
2050	2170	Lime		
2170	3480	Shale-Lime	0° - 2500'	
3480	3537	Lime	0° - 3500'	
3537	3577	Shale-Lime		
3577	3653	Lime		
3653	3695	Lime-Conglomerate		
3695	3724	Conglomerate		
3724	3773	Shale-Lime	0° - 3750'	Ran Halliburton Guard Log.

CASING LEFT IN HOLE AFTER COMPLETION

Set 187.92' of 8-5/8" OD Surface Casing.

STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

The undersigned certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Jay H. Galloway
 Jay H. Galloway

Subscribed and sworn to before me this 29th day of September, 1955.

My commission expires: 5/20/59

Vicky Jacobs
 Notary Public

10-1-1955

PLUGGING
 FILE SEC 15 T 12 R 17w
 BOOK PAGE 4 LINE 40