


15-051-00577-00-00
WELL PLUGGING RECORD



Ellis County. Sec. 16 Twp. 12 Rge. 17 (E) (W)
Location as "NE/CNW&SW¼" or footage from lines. NW NW NE
Lease Owner Isern Brothers etal
Lease Name Bemis Well No. 1
Office Address Box 45, Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed August 12, 1957 19
Application for plugging filed August 12, 1957 19
Application for plugging approved August 12, 1957 19
Plugging commenced August 12, 1957 19
Plugging completed August 12, 1957 19
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3792 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Pipe	0	221'	8-5/8"	221'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 550'.
Bridged hole at 550', ran 25 sacks
cement. Bridged hole at 210', ran
25 sacks cement. Bridge hole at
40', ran 10 sacks cement. Plug 40'
to base of cellar.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Isern Drilling Company
Address Box 45, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON
I. M. M. Shropshire (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) I. M. M. Shropshire
Lyons, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of August, 1957
George A. Meyer Notary Public.
STATE CORPORATION COMMISSION

My commission expires Feb. 10, 1959.

PLUGGING
FILE SEC 16 T. 12 R. 17W
BOOK PAGE 36 LINE 45

8-15-1957
AUG 15 1957
CONSERVATION DIVISION
Wichita, Kansas

15-051-00577-00-00

WELL LOG

ISERN BROTHERS ETAL, OWNER - BEMIS #1
NW/4 NW/4 NE/4 Section 16, Township 12, Range 17W,
Ellis County, Kansas

Figures indicate bottom of formation:

ELEVATION: 2154 DF	0	to	60	rock
			100	shale
PIPE RECORD:			560	shale & shells
8-5/8" set 221°			600	sand
Cemented with 150 sacks cement,			820	shale & shells
300# Calcium Chloride			1005	sand
August 2, 1957			1165	shale & shells
			1384	red rock
			1414	Anhydrite
			1710	shale & shells
			1920	salt
			2000	shale & shells
			2815	lime & shale
			2985	shale & shells
			3300	lime & shale
			3415	lime
			3555	lime & shale
			3704	lime
Rotary Commenced 8-2-57			3792	Arbuckle
Completed 8-12-57			3792	Rotary Total
				Depth D&A

STATE OF KANSAS)
COUNTY OF BARTON) SS

I, M. M. Shropshire, Drilling Superintendent of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

M. M. Shropshire

Subscribed and Sworn to before me this 13th day of August, 1957.

George A. Meyer

Notary Public
STATE CORPORATION COMMISSION

8-15-1957
AUG 15 1957

My commission expires Feb. 10, 1959.

PLUGGING
FILE SEC 16 T. 12 R. 17W
BOOK PAGE 36 LINE 45

CONSERVATION DIVISION