

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

15-051-20051-00-00  
WELL PLUGGING RECORD

Ellis County, Sec. 26 Twp. 12S Rge. 17 (W)

Location as "NE/CNW4SW4" or footage from lines NE SW SW

Lease Owner Herman George Kaiser, Oil Producer

Lease Name HOFFMAN Well No. 1

Office Address 909 Palace Building - Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-26 1967

Application for plugging filed 4-26 1967

Application for plugging approved 4-26 1967


Plugging commenced 4-26 1967

Plugging completed 4-26 1967

Reason for abandonment of well or producing formation No oil or gas found in commercial quantities.

If a producing well is abandoned, date of last production -- 19--

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas

Producing formation None Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN  | PULLED OUT |
|-----------|---------|------|----|--------|---------|------------|
|           |         |      |    | 8-5/8" | 215.11' | -0-        |
|           |         |      |    |        |         |            |
|           |         |      |    |        |         |            |
|           |         |      |    |        |         |            |
|           |         |      |    |        |         |            |
|           |         |      |    |        |         |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug to 500'. Cement through drill pipe with 20 sacks. Mud back to 210', cement with 20 sacks. Mud back to 40', set solid bridge and capped with 10 sacks, 2 sacks in rat hole. Plugging completed at 1:00 P.M., 4-26-67.

5-12-1967  
MAY 12 1967

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.  
Address 1425 Wichita Plaza - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Wilson Rains (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains  
1425 Wichita Plaza - Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 28 day of April, 1967

My commission expires March 3, 1970 Mary J. Brown Notary Public.

15-051-20051-00-00  
ROTARY DRILLING LOG

Operator: Herman Geo. Kaiser  
#1 HOFFMAN  
NE SW SW Sec. 26-12S-17W  
Ellis County, Kansas

Contractor: Rains & Williamson  
Oil Co., Inc.

Commenced: 4-21-67  
Completed: 4-26-67

Remarks: Set 8-5/8" surface  
casing at 215.11' w/  
150 sacks cement.

Formations

|                            |       |
|----------------------------|-------|
| Rock                       | 45'   |
| Shale                      | 875'  |
| Sand                       | 965'  |
| Shale                      | 1310' |
| Anhydrite                  | 1356' |
| Shale                      | 1960' |
| Lime and Shale             | 2400' |
| Lime                       | 2645' |
| Shale and Lime             | 2795' |
| Lime and Shale             | 3360' |
| Rotary Total Depth (D & A) | 3360' |

RECEIVED  
STATE CORPORATION COMMISSION  
5-12-1967  
MAY 12 1967


CONSERVATION DIVISION  
Wichita, Kansas

We certify the above log is  
true and correct to the best of  
our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.

  
Wilson Rains

Subscribed and sworn to before me, a Notary Public in and for the State of  
Kansas, County of Sedgwick, this 28th day of April, 1967.

  
Mary J. Brown Notary Public

My Commission Expires:  
March 3, 1970