

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-00226-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Ellis County, Sec. 26 Twp. 12 Rge. 17 (X) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW

Lease Owner Musgrove Petroleum Corporation

Lease Name Hoffman Well No. 1

Office Address 518 Petroleum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 1, 1953 19 53

Application for plugging filed February 9, 19 53

Application for plugging approved 19

Plugging commenced February 1, 19 53

Plugging completed February 1, 19 53

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3711 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	186.64'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 180' with heavy mud, bottom plug set at 180' with 1/2 sack of hulls and 20 sacks of cement.
Second plug set at 40' with 1/2 sack of hulls and 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bill Hay Drilling Company
Address Hosington, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
518 Petroleum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of February, 19 53
Mary S. Dunn
Notary Public.

My commission expires November 14, 1956.

24-2675-5 2-52-20M

2-11-1953

PLUGGING
FILE SEC 26 T 12 R 1724
BOOK PAGE 77 LINE 45

15-051-00226-00-00

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Bill Hay Drilling Company
 FARM: Hoffman #1
 LOCATION: SE SE SW Section 26-12-17
 Ellis County, Kansas

COMMENCED: January 19, 1953
 COMPLETED: February 1, 1953

0	400	Shale and shells
400	460	Sand
460	710	Shale and shells
710	885	Sand and shale
885	1160	Shale
1160	1290	Shale and pyrite
1290	1335	Anhydrite
1335	1365	Shale and lime shells
1365	2215	Shale and lime
2215	2485	Lime
2485	2625	Lime and shale
2625	2900	Lime
2900	3230	Lime and shale
3230	3640	Lime
3640	3675	Conglomerate
3675	3711	Arbuckle
	3711	Rotary Total Depth

Set 186.64' of 8 5/8" with 125 sacks of cement.

Dry and abandoned.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Bill Hay, do hereby certify that the above and foregoing is a true and correct copy of the log of the Hoffman #1, Section 26-12-17, Ellis County, Kansas, as reflected by the files of the Bill Hay Drilling Company.

BILL HAY DRILLING COMPANY

By Bill Hay

Subscribed and sworn to before me a Notary Public in and for Sedgwick County, Kansas this 9th day of February, 1953.

Mary Edmund
Notary Public

My Commission Expires: November 14, 1956.

2-11-1953

PLUGGING
 FILE REC 267-12 R 17-21
 BOOK PAGES 72 LINE 45