


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-051-00705-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Ellis County. Sec. 26 Twp. 12 Rge. 17 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE/4 NE/4 NW/4
Lease Owner Anschutz Drilling Company, Inc.
Lease Name Miller Well No. 1
Office Address 612 Union Nat'l Bk Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-16 1949
Application for plugging filed via telephone 8-16 1949
Application for plugging approved " 8-16 1949
Plugging commenced 8-17 1949
Plugging completed 8-18 1949
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19...
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3835 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	152'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from...feet to...feet for each plug set.

bottom plug 150' 15 sacks cemented through drill pipe
top plug 30' 10 sacks
job started 12:00 midnight, completed @ 1:00 A.M.

8-24-1949

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Anschutz Drilling Company, Inc.
Address 612 Union National Bank Building, Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Fred B. Anschutz (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Fred B. Anschutz
612 Union Nat'l Bk Bldg., Wichita, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 1949

Martha G. Gays Notary Public.

My commission expires 9-12-49

22-5133-s 9-48-10M



Well Log - Miller NE/4 NE/4 NW/4
26-12-17 Ellis Co, Ks.

Commenced: Aug 4, 1949
Completed: Aug 18, 1949

0	40	Surface clay
40	152	Surface clay
152	350	Shale
350	625	Shale - shells
625	720	Sand - shale
720	810	Shale - shells
810	905	Sand
905	965	Sand
965	1325	Shale, shells
1325	1350	Red Bed
1350	1395	Anhydrite
1395	1515	Shale
1515	1525	Pyrite
1525	1660	Shale - shells
1660	1745	Shale - shells
1745	2020	Shale - shells
2020	2150	Lime - shale
2150	2290	Lime - shale
2290	2360	Lime - shale
2360	2460	Lime - shale
2460	2505	Lime - shale
2505	2690	Lime - shale
2690	2700	Lime - shale
2700	2795	Lime - shale
2795	2865	Lime - shale
2865	2995	Lime - shale
2995	3115	lime - shale
3115	3195	Lime @ shale
3195	3252	Lime - shale
3252	3305	Lime
3305	3350	Lime
3350	3388	Lime
3388	3450	Lime
3450	3510	Lime
3510	3565	Lime
3565	3605	Lime
3605	3665	Lime
3665	3714	Lime
3714	3770	Conglomerate
3770	3785	Conglomerate
3785	3814	Arbuackle
3814	3835	Lime
3835	T.D.	

STATE OF KANSAS) SS
COUNTY OF ELLIS)

I hereby affirm that the above and foregoing is a true and correct copy
of the log of the Miller #1, located NE/4 NE/4 NW/4 26-12-17 Ellis County, Ks.

ANSCHUTZ DRILLING CO INC

Fred B. Anschutz
By Fred B. Anschutz

Subscribed and sworn to before me, a Notary Public, this 22 day of August, 1949

8-24-1949

My Commission expires April 22, 1950

Margaret Ring
.....
Margaret Ring

